

AD-A109 798

FLAHERTY-GIAVARA ASSOCIATES NEW HAVEN CT

F/G 13/13

NATIONAL DAM SAFETY PROGRAM. WHETSTONE GULF STORAGE DAM (INVENT--ETC(U)


JUL 81 H C FLAHERTY

DACW51-81-C-8006

NI

UNCLASSIFIED


1 OF 2  
AD A  
109 798



1 OF 2

AD A

109798



AD A109798

BLACK RIVER BASIN

LEVEL II

# WHETSTONE GULF STORAGE DAM

LEWIS COUNTY, NEW YORK  
INVENTORY No. NY. 544

## PHASE I INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM



RECEIVED  
JAN 20 1982  
E

APPROVED FOR PUBLIC RELEASE;  
DISTRIBUTION UNLIMITED

NEW YORK DISTRICT, CORPS OF ENGINEERS  
JULY 1981

DTC FILE COPY

8

01 19 82 067

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	4D-A109 718	
4. TITLE (and Subtitle) Phase I Inspection Report Whetstone Gulf Storage Dam Black River Basin, Lewis County, N.Y. Inventory No. 544		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s) HUGH C. FLAHERTY		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS Flaherty-Giavara Associates One Columbus Plaza New Haven, CT 06510		8. CONTRACT OR GRANT NUMBER(s) DACW51-81-C-0006
11. CONTROLLING OFFICE NAME AND ADDRESS Department of the Army 26 Federal Plaza New York District, CoE New York, New York 10287		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza New York District, CoE New York, NY 10287		12. REPORT DATE
		13. NUMBER OF PAGES
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; Distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Geology, Structural Stability Whetstone Gulf Storage Dam Lewis County Black River Basin		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report contains a visual inspection and analysis on the physical condition of the dam. The information and analysis are based on visual inspection of the dam by the performing organization.  Examination of available documents and a visual inspection of the dam did not reveal conditions which constitute an immediate hazard to human life or property. However, the dam has some deficiencies that need to be evaluated and remedied.		

Using the Corps of Engineers' screening criteria for the initial review of spillway adequacy, it has been determined that the embankment would be overtopped by all storms exceeding 71 percent of the Probable Maximum Flood (PMF). Consequently, the spillway cannot adequately discharge the peak outflow from the full PMF, however, it will pass one half the PMF. Therefore, the spillway is adjudged to be inadequate.

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Accession No.	
How	<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>
By	
Date	
Place	
Author	
Title	
Subject	
Notes	
Index	
Classification	
Remarks	

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
WHETSTONE GULF STORAGE DAM  
INVENTORY NO. NY 544  
BLACK RIVER BASIN  
LEWIS COUNTY, NEW YORK

TABLE OF CONTENTS

	<u>PAGE NO.</u>
ASSESSMENT	-
OVERVIEW PHOTOGRAPH	-
LOCATION MAP	i
1 - PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	4
2 - ENGINEERING DATA	6
2.1 GEOTECHNICAL DATA	6
2.2 DESIGN RECORDS	6
2.3 CONSTRUCTION RECORDS	7
2.4 OPERATION RECORDS	7
2.5 EVALUATION OF DATA	7
3 - VISUAL INSPECTION	8
3.1 FINDINGS	8
3.2 EVALUATION OF OBSERVATIONS	10
4 - OPERATION AND MAINTENANCE PROCEDURES	11
4.1 PROCEDURE	11
4.2 MAINTENANCE OF DAM	11
4.3 WARNING SYSTEM	11
4.4 EVALUATION	11

5 - HYDROLOGIC/HYDRAULIC	12
5.1 DRAINAGE AREA CHARACTERISTICS	12
5.2 ANALYSIS CRITERIA	12
5.3 SPILLWAY CAPACITY	13
5.4 RESERVOIR CAPACITY	13
5.5 FLOODS OF RECORD	13
5.6 OVERTOPPING POTENTIAL	14
5.7 EVALUATION	14
6 - STRUCTURAL STABILITY	15
6.1 EVALUATION OF STRUCTURAL STABILITY	15
6.2 STRUCTURAL STABILITY ANALYSIS	15
7 - ASSESSMENT/RECOMMENDATIONS	18
7.1 ASSESSMENT	18
7.2 RECOMMENDED MEASURES	18

#### APPENDICES

- A. PHOTOGRAPHS
- B. VISUAL INSPECTION CHECKLIST
- C. HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS
- D. STRUCTURAL STABILITY ANALYSIS
- E. PREVIOUS INSPECTION REPORTS/AVAILABLE DOCUMENTS
- F. REFERENCES
- G. DRAWINGS



PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Whetstone Gulf Storage Dam  
State Located: New York  
County: Lewis  
Watershed: Black River Basin  
Watercourse: Whetstone Creek  
Date of Inspection: April 10, 1981

ASSESSMENT

Examination of available documents and a visual inspection of the dam did not reveal conditions which constitute an immediate hazard to human life or property. However, the dam has some deficiencies that need to be evaluated and remedied.

Using the Corps of Engineers' screening criteria for the initial review of spillway adequacy, it has been determined that the embankment would be overtopped by all storms exceeding 71 percent of the Probable Maximum Flood (PMF). Consequently, the spillway cannot adequately discharge the peak outflow from the full PMF, however, it will pass one half the PMF. Therefore, the spillway is adjudged to be inadequate.

It is recommended that the following additional investigation be performed by a registered professional engineer engaged by the owner:

1. Investigate the wet, swampy areas at the downstream toe of slope of the right embankment, especially during dry summer months and when the reservoir operation level is high, to determine if they are still present, and if so, are they a result of seepage through the embankment. If seepage is occurring, the cause should be investigated and remedial actions undertaken, if necessary.


It is recommended that within 3 months of the final approval date of this report, the additional investigation should be initiated and within 18 months, appropriate remedial measures should be completed.

The following remedial measures should be completed within 12 months to correct existing deficiencies:


1. In order to provide sufficient freeboard along the entire length of dam, fill and regrade the depressed areas adjacent to both spillway abutments to their original level and cross section as shown on the plans in Appendix G. Strip all topsoil, and remove all brush and trees prior to filling these areas, and reseed or sod the areas after filling.
2. Clear the brush and trees from the embankments, including stump removal and backfilling, establish a vegetative cover, and cut the grass and weeds on the embankments at least annually.
3. Fill in any animal burrows on the embankment slopes.
4. Develop and implement a flood warning and emergency evacuation plan to alert downstream residents in the event conditions occur which could result in failure of the dam.
5. A program for regular maintenance should be developed and implemented.

Submitted by:

FLAHERTY GIAVARA ASSOCIATES, P.C.

  
Hugh C. Flaherty, P.E. & L.S.  
Chairman of the Board  
New York License No. 58508

Approved by:


  
Richard E. Mayo, L.E.  
for Col. W. M. Smith, Jr.  
New York District Engineer

Date:

17 SEPT 1981



PHOTO #1: Overview of  
Whetstone Gulf Storage Dam  
Inventory No. NY 544



## LOCATION MAP

WHETSTONE GULF STORAGE DAM  
 INVENTORY No. NY 544  
 BLACK RIVER BASIN  
 LEWIS COUNTY  
 MARTINSBURG, NEW YORK

FLAHERTY • GIAVARA ASSOCIATES, P.C.

NATIONAL DAM SAFETY PROGRAM  
PHASE I INSPECTION REPORT  
WHETSTONE GULF STORAGE DAM  
INVENTORY NO. NY 544  
D.E.C. NO. 101B-2862  
BLACK RIVER BASIN  
LEWIS COUNTY, NEW YORK

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I Inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367. Flaherty Giavara Associates, P.C. has been retained by the New York District to inspect and report on selected dams in the State of New York. Authorization and notice to proceed was issued to Flaherty Giavara Associates, P.C. under a letter of December 24, 1980 from W. M. Smith Jr., Colonel, Corps of Engineers. Contract No. DACW 51-81-C-0006 has been assigned by the Corps of Engineers for this work.

b. Purpose

Evaluation of the existing conditions of the subject dam to identify deficiencies and hazardous conditions, determine if they constitute hazards to life and property and recommend remedial measures where necessary.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances

The Whetstone Gulf Storage Dam consists of earthen embankments separated by a concrete overflow spillway located slightly to the left of the center of the dam. The overall length of the dam is 301 feet. Plans, profiles, and sections of the dam prepared in 1960 by the New York State Conservation Department, Division of Lands and Forests, Bureau of Camps and Trails, are included in Appendix G.

The earthen embankment is approximately 17 feet high adjacent to the spillway structure. The downstream slopes are approximately 1.5 horizontal to 1 vertical for the embankment left of the overflow spillway and 4 to 1 for the right embankment. The embankments are constructed of

compacted "mineral soil" as indicated by the Item Specifications in Appendix E. A concrete cutoff wall projects across the upstream slope of the embankment, the top of which is elevation 1899.0 (NGVD). It was designed to extend to a depth of at least 3 feet below the original ground surface. There is riprap on the upstream slope below the cutoff wall. The upstream slopes above the cutoff wall are grass and brush-covered, as are the downstream slopes. Toe drains were not constructed along the embankment.

The concrete overflow spillway is 60 feet wide and 12 feet high from the apron to the crest; the spillway crest is at elevation 1898.0 (NGVD) and the downstream apron is at elevation 1886.0 (NGVD). The spillway is equipped with a 3 foot square gated orifice at the streambed level. Underdrains were installed beneath the spillway apron and weep holes were incorporated into the downstream spillway abutments. The tops of the abutments are at elevation 1903.1 (NGVD), which is 5.1 feet above the weir crest level. The walls extend upstream to join with the cutoff wall, then angle out and away from the spillway to form retaining walls for the approach channel. In the downstream direction, the walls extend to the end of the spillway apron.

b. Location

The Whetstone Gulf Storage Dam is located off an unimproved road approximately 5.7 miles southwest of the village of Glenfield in the Town of Martinsburg, New York. The dam is located at latitude north 43°-41.0' and longitude west 75°-30.5' on the U.S. Geological Survey 7.5 minute series topographic map "Page, New York". The Location Map on page i indicates where the dam is situated.

c. Size Classification

The maximum height of the dam is 23 feet and the maximum storage capacity is 3742 acre-feet at the top of dam. Therefore, Whetstone Gulf Storage Dam is classified as an "Intermediate" dam as defined by the Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification

There are ten roads (including New York State Routes 12 and 12D/26), approximately 2 dwellings, 4 buildings and the Whetstone Gulf State Park campground and bathing area (See Photo No. 28) within the dam failure flood hazard area. Therefore, the dam is in the "High" hazard category as defined by the Recommended Guidelines for Safety Inspection of Dams.

e. Ownership

The dam is owned by the State of New York and administered by the Thousand Islands Park Commission. The addresses and telephone numbers are as follows:

Owner

Contact: Mr. Roger Frary  
Senior Park Engineer  
Thousand Islands Regional Office  
Keewaydin State Park  
Alexandria Bay, New York 13607

Telephone: (315) 482-2593

Contact: Mr. Robert Berry  
Park Foreman  
Whetstone Gulf State Park  
R.D. 2  
Lowville, New York 13367

Telephone: (315) 376-6630

f. Purpose

The primary purposes of this dam are flood control and regulation of the water level of Whetstone Creek for recreational use.

g. Design and Construction History

The dam was designed in 1960 by the New York State Conservation Department, Division of Lands and Forests, Bureau of Camps and Trails. It was constructed in 1961 by the Law Brothers Contracting Corporation of Lyons Falls, New York. The only post construction modification noted was the grouting of cracks located in the downstream face of the overflow spillway and in the crest of the overflow spillway weir with epoxy cement in the fall of 1975.

h. Normal Operating Procedure

The only regular operating procedures in effect for this dam involve opening or closing the reservoir drain to regulate stream flow in Whetstone Creek. The normal water level in the lake is maintained by the crest elevation of the overflow spillway weir at 1898.0 (NGVD).

### 1.3 PERTINENT DATA

- a. Drainage Area (Square Miles) 8.09
- b. Discharge at Dam Site (CFS)
  - Top of Dam 2186
  - Crest of Overflow Spillway 140
  - Reservoir Drain Inlet -
- c. Elevations (NGVD)
  - Top of Dam 1903.1
  - Crest of Overflow Spillway 1898.0
  - Reservoir Drain Inlet 1886.0
- d. Reservoir Surface Area (Acres)
  - Top of Dam 640
  - Crest of Overflow Spillway 385
- e. Storage (Acre-Feet)
  - Top of Dam 3742
  - Crest of Overflow Spillway 1446
- f. Dam
  - Type: Earthfill with a concrete core wall
  - Length (Feet) 301
  - Upstream Slope (H:V) 1.5-2.0:1
  - Downstream Slope (H:V) 1.5-4.0:1
  - Crest Width (Feet) 10
- g. Overflow Spillway
  - Type: Concrete weir with concrete wingwalls, abutments and apron
  - Length (Feet) 60
  - Width (Feet) 49
  - Side Slopes (H:V) vertical
  - Channel Bottom Slopes (Feet/Foot) upstream -  
downstream (apron) level
  - Control: None
- 1. Reservoir Drain
  - Type: 36 inch high by 36 inch wide square opening in



spillway (7 feet long)

- Control: 36 inch by 36 inch  
slide gate

## SECTION 2 - ENGINEERING DATA

### 2.1 GEOTECHNICAL DATA

#### a. Geology

The Whetstone Gulf Storage Dam is located on Whetstone Creek, a northeasterly flowing tributary to the Black River, about 5.7 miles southwest of Glenfield in the Tug Hill Plateau physiographic province of New York State. The plateau has a summit elevation of approximately 2000 feet above mean sea level.

The caprock of the plateau is the Oswego Sandstone of the Late Ordovician age. The Oswego is approximately 100 feet thick and consists of greenish-gray, thin to thick-bedded, fine to medium-textured, cross-bedded sandstone, with interbedded seams of red, green, and gray shales.

The region was glaciated during the Pleistocene Epoch, the latest advance being the Wisconsin stage. As the glacier retreated, it deposited a heterogenous layer of clay, silt, sand, gravel, and rock debris known as glacial till over the bedrock surface.

#### b. Subsurface Conditions

The "Foreword" section of an undated, untitled report (containing Item Specifications) refers to test pits excavated at the site. It is not known if records of the test pit locations and logs were prepared; however, none were available for review. The above report states "Test pits revealed no evidence of bedrock at the dam site nor (were) there other evidences of bedrock in the vicinity of the dam site. Under 9 to 12 inches of top soil the soil is a fairly impervious mixture of clay and gravel."

Based on this description, the clay and gravel is believed to be glacial till. Therefore, it is assumed that the dam embankment and overflow spillway are bearing on glacial till and that the embankment portions of the dam were constructed of glacial till.

### 2.2 DESIGN RECORDS

This dam was designed in 1960 by the New York Conservation Department, Division of Lands and Forests, Bureau of Camps and Trails. Some hydrologic/hydraulic and structural design information is included in Appendix E. No other design records were obtained.

### 2.3 CONSTRUCTION RECORDS

This dam was constructed in 1961 by the Law Brothers Contracting Corporation of Lyons Falls, New York. The contract drawings and specifications which were prepared by the New York Conservation Department, Division of Lands and Forests, Bureau of Camps and Trails, are included in Appendix G. No other construction records were obtained.

### 2.4 OPERATION RECORDS

No operation records were obtained for this dam.

### 2.5 EVALUATION OF DATA

The data presented herein was obtained primarily from the files of the New York State Department of Environmental Conservation (DEC). This information appears to be reliable and adequate for the purposes of a Phase I Inspection Report.

## SECTION 3 - VISUAL INSPECTION

### 3.1 FINDINGS

#### a. General

A visual inspection of the Whetstone Gulf Storage Dam was conducted on April 10, 1981. The weather was sunny and the temperature was 60+°F. At the time of the inspection, water was flowing in the overflow spillway (See Photos No. 5, 7 and 10) and also in the reservoir drain (See Photo No. 15).

#### b. Dam

The dam has an embankment section on each side of the overflow spillway (See Photos No. 3 and 4) with a concrete core wall within each section (See Photos No. 22 and 23); these embankments are generally in good condition. There is no visible evidence of lateral movement, major erosion, or other serious defects.

The following specific items were noted:

1. The embankment crest sloped downward for a distance of 25 to 30 feet along the left embankment toward the spillway abutment to a point 2.5 feet below and immediately adjacent to the left spillway abutment (See Photo No. 3). Adjacent to the right spillway abutment, the crest sloped downward over a length of 10 to 12 feet to a point 1.6 feet below the right spillway abutment. Beyond these sloping areas, the crest appeared to be at approximately the same elevation as the top of the spillway abutments.
2. Minor surface erosion has occurred, particularly in footpaths on the embankment crest and on the upstream and downstream slopes adjacent to the spillway abutments.
3. Considerable portions of the crest, the downstream slope and the upstream slope above the cutoff wall were covered with brush and small trees (See Photos No. 3, 4 and 22).
4. Several wet, spongy areas were observed along the toe of the downstream embankment between the overflow spillway and right abutment (See Photo No. 25). No flow or seepage was detected. It is probable that these wet areas were due to frost or snow melt or to runoff from the right abutment area.

5. Several animal burrows were observed on the right embankment, some near the downstream toe of slope and others on the upstream slope near the crest.

c. Overflow Spillway

The overflow spillway consists of a 60 foot long broad-crested concrete weir with wingwalls, abutments and an apron, all of which are in good condition (See Photos No. 6, 7, 8, 10 and 12). Sealed cracks were observed in the crest and the downstream face of the overflow spillway (See Photos No. 18 and 19). Reportedly, these cracks were repaired with epoxy cement in the fall of 1975. The concrete wingwalls flare out at 45° to the abutments to form the approach to the overflow spillway. A one quarter inch crack has developed at the junction of the right upstream abutment and core wall (See Photo No. 21). Each concrete abutment has four 3 inch diameter weep holes located downstream of the spillway face (See Photo No. 16). The weep holes for the left downstream abutment had a very minor flow (See Photo No. 17). The 60 foot wide concrete apron extends 35.5 feet downstream from the face of the spillway and has two 12 inch high by 12 inch wide longitudinal sills, one of which has a few cracks (See Photo No. 20). In addition, minor undermining of the downstream end of the apron at the right abutment has occurred (See Photo No. 24).

d. Reservoir Drain

The reservoir drain is a 36 inch high by 36 inch wide square opening in the concrete spillway (See Photo No. 15) which is controlled by a 36 inch slide gate and hand-wheel (See Photo No. 14) which was partially open at the time of inspection (See Photo No. 15).

e. Downstream Channel

The natural channel downstream of the dam has a width of 20+ feet and a depth of 8 inches (See Photo No. 26). The channel bed is gravel with grassed and wooded side slopes and appeared to be stable at the time of inspection.

Approximately one half mile downstream of the dam, the creek flows through a steep ravine called Whetstone Gulf (See Photo No. 27) for a distance of 2+ miles before it reaches the Whetstone Gulf State Park campground and bathing area (See Photo No. 28).

f. Reservoir - Storage Pool Area

The reservoir is bordered by relatively flat woodlands (See Photo No. 2). There is no significant possibility

of landslides into the reservoir affecting the safety of the dam.

### 3.2 EVALUATION OF OBSERVATIONS

The visual inspection revealed some deficiencies on this structure. The following observations were made:

- a. The embankment crest sloped downward toward the spillway abutments on either side of the spillway.
- b. Minor surface erosion was noted on the embankment crest and slopes.
- c. Considerable portions of the embankment were covered by brush and small trees.
- d. Several wet, spongy areas were observed along the toe of the right downstream embankment slope.
- e. Minor undermining of the downstream end of the spillway apron was evident at the right spillway abutment.
- f. Cracks were noted at the junction of the right upstream spillway abutment and core wall and in the right longitudinal sill of the spillway apron.

## SECTION 4 - OPERATION AND MAINTENANCE PROCEDURES

### 4.1 PROCEDURES

The normal water surface level is maintained by the crest of the overflow spillway weir at elevation 1898.0 (NGVD). The only operational procedure in effect at this time is the opening or closing of the reservoir drain to regulate stream flow in Whetstone Creek.

### 4.2 MAINTENANCE OF DAM

There was no evidence of any routine maintenance operations at the Whetstone Gulf Storage Dam; however, cracks in the crest and downstream face of the overflow spillway were grouted with epoxy cement in the fall of 1975. In addition, spalling and erosion of the lower portion of the right concrete spillway abutment near the outlet to the reservoir drain is scheduled for repair in the autumn of 1981 by the Thousand Island Parks Commission.

### 4.3 WARNING SYSTEM

No warning system is presently in effect.

### 4.4 EVALUATION

Presently, few maintenance procedures are in effect for this dam. Therefore, a program for regular maintenance should be developed and implemented.

## SECTION 5 - HYDROLOGIC/HYDRAULIC

### 5.1 DRAINAGE AREA CHARACTERISTICS

The dam is located in the Town of Martinsburg on Whetstone Creek, approximately 17,200 feet upstream of the campground at Whetstone Gulf State Park. Whetstone Creek joins the Black River near the village of Glenfield, approximately fifty-four miles upstream of Lake Ontario near Watertown, New York.

The watershed (shown on the Watershed Map on Page C-5 in Appendix C) consists of 5,180 acres (8.09 square miles) located on a high plateau with typical slopes of less than five percent. Land within the watershed is primarily undeveloped with extensive woodlands and some open fields. A large wetland (370+ acres) is located one mile upstream from the dam; however, no waterbodies are situated within the watershed.

The watercourse upon which the reservoir is located, is a perennial stream with a typical flow width of 20 feet and a typical flow depth of 12 inches.

### 5.2 ANALYSIS CRITERIA

The purpose of the hydrologic/hydraulic analysis is to evaluate the spillway capacity and the potential for overtopping. The analysis of the spillway capacity of the dam and storage of the reservoir was performed using the Corps of Engineers' HEC-1 Computer Model - Dam Safety Version. The procedure included determining the Probable Maximum Flood (PMF) runoff from the watershed and routing the inflow hydrograph through the impoundment to determine the outflow hydrograph. The unit hydrograph was defined by the Snyder Synthetic Unit Hydrograph method, and the Modified Puls routing procedure was incorporated.

The initial rainfall loss was assumed to be 1.0 inches, and the uniform rainfall loss was assumed to be 0.1 inches per hour. In accordance with recommended guidelines of the Corps of Engineers, the Probable Maximum Precipitation (PMP) was 18.6 inches (24 hour duration, 200 square mile area).

The analysis was conducted for both the full PMF and for several fractional PMF conditions. The PMF inflow of 9,813 CFS was routed through the reservoir and the peak outflow was determined to be 4,876 CFS.



### 5.3 SPILLWAY CAPACITY

The total outlet capacity is the discharge from the overflow spillway.

The overflow spillway consists of a 60 foot long broad-crested reinforced concrete weir and a reinforced concrete discharge apron with one foot high by one foot wide longitudinal sills.

The stage discharge data for the spillway capacity was calculated for the stages tabulated below:

<u>Stage (Feet)</u>	<u>Discharge Capacity (CFS)</u>	<u>Element of Structure</u>
1898.0	0	Overflow Spillway Crest
1899.0	180	--
1900.0	509	--
1900.6	755	Low Embankment Reach
1901.0	939	--
1901.8	1350	--
1902.0	1463	--
1902.3	1642	--
1902.7	1903	--
1903.0	2114	--
1903.1	2186	Top of Dam

The total spillway capacity at the top of dam is 2186 CFS.

### 5.4 RESERVOIR CAPACITY

The storage capacity of the impoundment was obtained from the "Capacity Curve" on sheet 2 of 5 of the contract drawings in Appendix G for the stages indicated below:

<u>Stage (Feet)</u>	<u>Storage (Acre-Feet)</u>	<u>Storage (Inches of Runoff)</u>
1898.0	1446	3.35
1903.1	3742	8.67

### 5.5 FLOODS OF RECORD

No data regarding flood levels was obtained for this dam; however, in the spring of 1972, heavy rains caused high discharge flows over the spillway (See Photos No. 9 and 11) and flooding downstream (See Photos No. 13 and 29).

## 5.6 OVERTOPPING POTENTIAL

The results of the HEC-1 DB computer analysis indicate that the crest of the dam is overtopped by all storms exceeding 71 percent of the PMF event. The PMF discharge rate of 4,876 cubic feet per second (CFS) would occur at a peak flood stage of 1904.8 feet, which is 1.7 feet above the crest of the dam.

The results of the analysis are tabulated below:

<u>Flood Condition</u>	<u>Peak Inflow (CFS)</u>	<u>Peak Outflow (CFS)</u>	<u>Maximum Stage Elevation (NGVD)</u>
0.5 PMF	4907	1110	1901.3
1.0 PMF	9813	4876	1904.8

## 5.7 EVALUATION

Using the Corps of Engineers' screening criteria for the initial review of spillway adequacy, it has been determined that the capacity of the overflow spillway is not adequate to pass the full PMF, but it will pass one half the PMF; approximately 71 percent of the PMF can be safely passed before overtopping will occur. The PMF event would overtop the dam for a duration of 11 hours and the maximum depth of flow over the crest would be 1.7 feet. Therefore, the spillway is adjudged to be inadequate.

## SECTION 6 - STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

#### a. Visual Observations

There was no visible evidence of major erosion, lateral movement, structural deterioration or other signs of overall structural instability of the dam during the site examination. The embankment crest was found to be irregular, sloping downward to the overflow spillway structure; however, there was no evidence that this irregular level is the result of foundation or embankment settlement. Therefore, based on the conditions that were observed, there is no reason to question the static structural stability of the dam.

#### b. Design and Construction Data

There is no construction data to confirm the actual physical properties and configuration of the earthfill in the embankments. However, the dam proportions are considered to be reasonable for the soils that were available at the site and therefore, the dam would be expected to have adequate safety margins with respect to stability under static loading conditions.

#### c. Operating Records

No operating records were obtained for Whetstone Gulf Storage Dam.

#### d. Post Construction Changes

Contract drawings for the Whetstone Gulf Storage Dam in Appendix G show a configuration and cross section for the dam embankment consisting of an 8 foot wide crest, 3 horizontal to 1 vertical upstream slopes above the cutoff wall and approximately 5 to 3 slopes for the riprap slope below and downstream slopes are shown to be 2 to 1. The actual constructed section has a wider crest and the downstream slope of the left embankment and both upstream slopes are steeper than shown on the contract drawings.

### 6.2 STRUCTURAL STABILITY ANALYSIS

Design drawings available for review show a plan, upstream and downstream elevation, and typical cross sections through the spillway, abutment and wingwall sections. Some previously performed stability computations (1960) are included on pages E-3 through E-7 in Appendix E; however, it is not certain that these analyses refer to the as-built conditions in the actual location of the dam. As part of the present

study, stability evaluations have been performed for the overflow spillway and the spillway abutments. Where information concerning the foundation materials or properties of the dam was not available, reasonable assumptions were made. The stability computations assumed a structural cross section based on dimensions indicated by the plans included in Appendix G of this report.

The stability analysis is presented in Appendix D. The results of the stability computations are summarized in the following table:

Loading Condition  (Spillway Section)	<sup>1</sup> Factors of Safety		<sup>3</sup> Location of Resultant Passing Through Base
	Over- turning	<sup>2</sup> Sliding	
1. Normal operating condition: water level 1 foot above spillway crest	2.74	2.49	0.36b
2. Maximum operating condition: water level at top of dam (5.1 feet above spillway crest)	2.62	2.14	0.39b
3. Full PMF condition: water level at El. 1904.8 (6.8 feet above spillway crest)	2.48	1.99	0.37b
4. Ice loading condition: 5.0 Kips per foot acting at top of spillway	1.44	1.50	0.17b
5. Seismic loading condition: water level at 1 foot above spillway crest plus seismic effects applicable to Zone 3	2.08	1.93	0.31b

<sup>1</sup>These factors of safety indicate the ratio of moments resisting overturning to those moments causing overturning, and the ratio of forces resisting sliding to those causing sliding.

<sup>2</sup>As determined applying the friction-shear method

<sup>3</sup>Indicated in terms of the base dimension of the dam (b), measured from the toe of the dam

Note: All loading conditions include an uplift force equal to  $\frac{2}{3}$  the height of the overflow spillway multiplied by the hydrostatic pressure acting upon it which was applied in conjunction with all overturning forces.

The analysis indicates that both the overflow spillway section and the abutment/wingwall sections are stable against overturning and sliding effects under normal operating conditions, maximum operating conditions and full PMF conditions. However, less than desirable overturning and sliding factors of safety result under ice loading conditions, but the continuous shear keys along the bottom and sides of the spillway combined with the spillway slope should add sufficient additional stability to offset the theoretical ice loading. Further stabilizing the spillway section are dowels extending from the abutment toe section.

The Whetstone Gulf Storage Dam is located in Seismic one 2, near the boundary with Zone 3 and in accordance with Phase I guidelines, the seismic stability analysis was performed for the overflow spillway assuming a seismic coefficient of 0.1 for normal conditions with the water level one foot above the spillway crest. As a result of this analysis, less than desirable safety factors for overturning and sliding were determined for these seismic loading conditions.

The discussed analyses apply to a dam in structurally good condition. The field observations indicate some surface cracks (which have been repaired) but no major structural faults which would significantly alter the stability or soundness of the structure.

## SECTION 7 - ASSESSMENT/RECOMMENDATIONS

### 7.1 ASSESSMENT

#### a. Condition

On the basis of the visual examination, there were no signs of impending structural failure or other conditions which would warrant urgent remedial action; however, there is a concern relative to first, the portions of the embankment crest which slope downward toward the overflow spillway structure and second, the wet areas at the downstream toe of the right embankment.

#### b. Adequacy of Information

The evaluation of this dam is based primarily on visual examination, reference to the 1960 contract drawings, approximate hydraulic and hydrologic computations, and application of engineering judgement. The available information that was obtained is adequate for the purposes of a Phase I assessment.

#### c. Need for Additional Investigations

It is recommended that the following additional investigation be performed by a registered professional engineer engaged by the owner:

1. Investigate the wet, swampy areas at the downstream toe of slope of the right embankment, especially during dry summer months and when the reservoir operation level is high, to determine if they are still present, and if so, are they a result of seepage through the embankment. If seepage is occurring, the cause should be investigated and remedial actions undertaken, if necessary.

#### d. Urgency

It is recommended that within 3 months of the final approval date of this report, the additional investigation described in Section 7.1c should be initiated and within 18 months, appropriate remedial measures should be completed. The recommended corrective measures presented in Section 7.2 should be completed within 12 months of final approval.


### 7.2 RECOMMENDED MEASURES

It is considered important that the following items be accomplished in addition to any items required as a result of the additional investigations recommended in Section 7.1c:

- a. In order to provide sufficient freeboard along the entire length of dam, fill and regrade the depressed areas adjacent to both spillway abutments to their original level and cross section, as shown on the plans in Appendix G. Strip all topsoil, and remove all brush and trees prior to filling these areas, and reseed or sow the areas after filling.
- b. Clear the brush and trees from the embankments, including stump removal and backfilling, establish a vegetative cover, and cut the grass and weeds on the embankments at least annually.
- c. Fill in any animal burrows on the embankment slopes.
- d. Develop and implement a flood warning and emergency evacuation plan to alert downstream residents in the event conditions occur which could result in the failure of the dam.
- e. A program for regular maintenance should be developed and implemented.

APPENDIX A  
PHOTOGRAPHS








PHOTO #2: Overview of impoundment




PHOTO #3: Crest of dam looking toward right abutment



PHOTO #4: Overview of upstream face of dam



PHOTO #5: Overview of downstream face of dam




PHOTO #6: Upstream face of dam



PHOTO #7: Downstream face of dam




PHOTO #8: Crest of spillway looking toward left abutment



PHOTO #9: Crest of spillway looking toward right abutment during flood in spring, 1972



PHOTO #10: Spillway from left downstream spillway  
abutment



PHOTO #11: Spillway from left downstream spillway  
abutment during flood in spring, 1972



PHOTO #12: Spillway apron and downstream channel conditions from spillway



PHOTO #13: Downstream channel conditions from spillway during flood in spring, 1972




PHOTO #14: Hand wheel (under wooden housing)  
and operating platform for 36 inch  
high by 36 inch wide reservoir drain




PHOTO #15: Reservoir drain outlet at downstream  
face of spillway






PHOTO #16: 3 inch diameter weep holes in left downstream spillway abutment



PHOTO #17: Close-up of 3 inch diameter weep hole (flowing)



PHOTO #18: Grouted crack in crest of spillway  
weir




PHOTO #19: Grouted crack in downstream face  
of spillway



PHOTO #20: Cracks in 12 inch high by 12 inch wide longitudinal sill



PHOTO #21: Crack at intersection of right upstream spillway abutment and core wall



PHOTO #22: Core wall in embankment section left  
of spillway



PHOTO #23: Core wall in embankment section right  
of spillway



PHOTO #24: Erosion at end of right downstream  
spillway abutment



PHOTO #25: Seepage at downstream toe of slope  
right of spillway



PHOTO #26: Downstream channel conditions



PHOTO #27: Aerial view of Whetstone Gulf  
(downstream of dam)




PHOTO #28: Bathing Pool Dam and appurtenant structures at Whetstone Gulf State Park (downstream of dam)



PHOTO #29: Bathing Pool Dam and appurtenant structures at Whetstone Gulf State Park (downstream of dam) during flood of spring, 1972

APPENDIX B  
VISUAL INSPECTION CHECKLIST



## VISUAL INSPECTION CHECKLIST

### 1) Basic Data

#### a. General

Name of Dam Whetstone Gulf Storage Dam  
Fed. I.D. # NY 544 DEC Dam No. 101B-2862  
River Basin Black  
Location: Town Martinsburg County Lewis  
Stream Name Whetstone Creek  
Tributary of Black River  
Latitude (N) 43°-41.0' Longitude (W) 75°-30.5'  
Type of Dam Earthfill embankment with a concrete overflow spillway  
Hazard Category High  
Date(s) of Inspection April 10, 1981  
Weather Conditions Sunny, 60° + F.  
Reservoir Level at Time of Inspection Elevation 1898.1 + (NGVD)

b. Inspection Personnel T. L. Ward & R. A. Criscuolo of Flaherty Giavara Associates,  
P. C.; J. J. Rixner & C. W. Eller of Haley & Aldrich, Inc.; B. McL. Whittingham of  
Salmon Associates

c. Persons Contacted (Including Address & Phone No.)  
Mr. Roger Frary, Senior Park Engineer      Mr. Robert Berry, Park Foreman  
Thousand Islands Regional Office      Whetstone Gulf State Park  
Keewaydin State Park      R. D. 2  
Alexandria Bay, New York 13607      Lowville, New York 13367  
(315) 482-2593      (315) 376-6630

#### d. History:

Date Constructed 1961 Date(s) Reconstructed Never  
Designer New York State Conservation Department, Division of  
Lands and Forests, Bureau of Camps and Trails  
Constructed By Law Brothers Contracting Corporation  
Owner State of New York (Thousand Islands Park Commission)

2) Embankment

a. Characteristics

- (1) Embankment Material Glacial Till
- (2) Cutoff Type Core wall to 3 feet below original ground
- (3) Impervious Core Concrete core wall with a top elevation of 1899.0(NGVD)
- (4) Internal Drainage System None observed
- (5) Miscellaneous No comments

b. Crest

- (1) Vertical Alignment Fair; surface generally irregular; crest slopes downward to a point 2.5 feet below the left spillway abutment and 1.6 feet below the right spillway abutment
- (2) Horizontal Alignment Good; substantially straight
- (3) Surface Cracks None observed
- (4) Miscellaneous Minor surface erosion along footpath; grass-covered; shrubs along edges

c. Upstream Slope

- (1) Slope (Estimate - V:H) 1:1.5-2.0
- (2) Undesirable Growth or Debris, Animal Burrows Brush, shrubs and several small trees behind concrete core wall; no animal burrows were noted
- (3) Sloughing, Subsidence or Depressions Minor surface erosion noted along spillway abutments

(4) Slope Protection Blocky stone riprap observed upstream of concrete  
core wall

(5) Surface Cracks or Movement at Toe None evident

d. Downstream Slope

(1) Slope (Estimate - V:H) 1:1.5 -4.0

(2) Undesirable Growth or Debris, Animal Burrows Brush, shrubs and numerous  
small trees; no animal burrows were noted

(3) Sloughing, Subsidence or Depressions Minor surface erosion along spillway  
abutments

(4) Surface Cracks or Movement at Toe None observed

(5) Seepage Wet area observed to the right of overflow spillway at downstream  
toe of slope; may be due to frost or snow melt

(6) External Drainage System (Ditches, Trenches, Blanket) None apparent

(7) Condition Around Outlet Structure Good; except for minor undermining  
of the downstream end of the concrete spillway apron at the right  
spillway abutment

(8) Seepage Beyond Toe None evident

e. Abutments - Embankment Contact

Left: Good condition

Right: Good condition

(1) Erosion at Contact None apparent

(2) Seepage Along Contact None evident

3) Drainage System

a. Description of System Broad-crested concrete weir and concrete apron

b. Condition of System Good; except for very minor surface cracks in concrete of spillway abutment and longitudinal sills of spillway apron

c. Discharge from Drainage System Concrete apron with longitudinal sills leading to natural discharge channel

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Peizometers, Etc.)  
None observed

5) Reservoir

- a. Slopes Relatively flat woodlands on plateau
- b. Sedimentation None observed
- c. Unusual Conditions Which Affect Dam None noted

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) Approximately 2 dwellings, 4 buildings, the Whetstone Gulf State Park campground and bathing area and ten roads (including New York State Routes 12 and 12D/26) are within the dam failure flood hazard area
- b. Seepage, Unusual Growth None observed
- c. Evidence of Movement Beyond Toe of Dam None evident
- d. Condition of Downstream Channel Good; streambed is gravel and channel has grassed and wooded side slopes.

7) Spillway(s) (Including Discharge Conveyance Channel)

- Overflow spillway and spillway apron
- a. General Overflow spillway handles all major flows; reservoir drain (3 foot high by 3 foot wide opening in spillway) handles normal flows
- b. Condition of Overflow Spillway Good; cracks in spillway crest and downstream spillway face have been grouted with epoxy cement

c. Condition of Emergency Spillway Not applicable

d. Condition of Spillway Apron Good; except for very minor undermining  
of the downstream end at the right spillway abutment and cracks in the  
longitudinal sills

8) Reservoir Drain/Outlet

Type: Pipe \_\_\_\_\_ Conduit \_\_\_\_\_ Other Square opening  
in spillway

Material: Concrete reinforced Metal \_\_\_\_\_ Other \_\_\_\_\_

Size: 36 inches high by 36 inches wide Length 7 feet

Invert Elevations: Entrance 1886.0 (NGVD) Exit 1886.0 (NGVD)

Physical Condition (Describe):

Unobservable \_\_\_\_\_

Material: Good

Joints: None Alignment Good

Structural Integrity: Appears to be good

Hydraulic Capability: Good

Means of Control: Gate 36" by 36"  
slide gate Valve \_\_\_\_\_ Uncontrolled \_\_\_\_\_

Operation: Operable \_\_\_\_\_ Inoperable \_\_\_\_\_ Uncontrolled \_\_\_\_\_

Present Condition (Describe): Good; slide gate is operated regularly to  
adjust stream flow

9) Structural

- a. Concrete Surfaces Concrete of the spillway crest, wingwalls, abutments and apron was in good condition with only minor surface cracks
- b. Structural Cracking No evidence of any structural cracks; only minor surface cracks, possible due to shrinkage
- c. Movement - Horizontal & Vertical Alignment (Settlement) None observed
- d. Junctions with Abutments or Embankments Good; however, a minor crack (one quarter inch wide) has developed in the top 2 inches of the right upstream spillway abutment at its junction with the core wall
- e. Drains - Foundation, Joint, Face Four 3 inch diameter weep holes located at left and right downstream spillway abutments (weep holes at left downstream abutment have continuous, very low volume flow); 12 inch high by 12 inch wide underdrain trenches drained by 4 inch diameter tile pipes provide drainage beneath the concrete spillway apron
- f. Water Passages, Conduits, Sluices Good condition; reservoir drain and slide gate are used regularly to adjust stream flows
- g. Seepage or Leakage No signs of seepage or leakage

- h. Joints - Construction, etc. Good condition
- i. Foundation Inaccessible
- j. Abutments See 9) d. above
- k. Control Gates 36 inch high by 36 inch wide slide gate controls the reservoir drain and is operated regularly to adjust the stream flow of Whetstone Creek
- l. Approach & Outlet Channels Upstream: wingwalls at 45 degrees to the spillway abutments are in good condition. Downstream: concrete spillway apron with longitudinal sills is in good condition except for the slight undermining and cracks described in 7) d. above
- m. Energy Dissipators (Plunge Pool, etc.) Reinforced concrete spillway apron
- n. Intake Structures Not applicable
- o. Stability Appears to be stable
- p. Miscellaneous No comments



10) Appurtenant Structures (Power House, Lock, Gatehouse, Other)

a. Description and Condition      None observed

This image shows a single sheet of white paper with horizontal ruling lines. The lines are evenly spaced and run across the width of the page. There is no handwriting or other markings on the paper.

APPENDIX C

HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS

CHECK LIST FOR DAMS  
HYDROLOGIC AND HYDRAULIC  
ENGINEERING DATA

AREA-CAPACITY DATA:

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	<u>1903.1</u>	<u>640</u>	<u>3742</u>
2) Design High Water (Max. Design Pool)	<u>--</u>	<u>--</u>	<u>--</u>
3) Overflow Spillway Crest	<u>1898.0</u>	<u>385</u>	<u>1446</u>
4) Pool Level with Flashboards	<u>--</u>	<u>--</u>	<u>--</u>
5) Reservoir Drain Invert	<u>1886.0</u>	<u>0</u>	<u>0</u>

DISCHARGES:

	<u>Volume</u> (cfs)
1) Average Daily	<u>Unknown</u>
2) Overflow Spillway @ Maximum High Water (Top of Dam)	<u>2186</u>
3) Emergency Spillway @ Design High Water	<u>--</u>
4) Principal Spillway @ Emergency Spillway Crest	<u>--</u>
5) Low Level Outlet @ Overflow Spillway Crest	<u>140</u>
6) Total (of all facilities) @ Maximum High Water	<u>2326</u>
7) Maximum Known Flood	<u>Unknown</u>
8) At Time of Inspection	<u>6 ±</u>

CREST:

ELEVATION: 1903.1 (NGVD)

Type Earthen embankment with a concrete core wall

Width 10 feet

Length 301 feet

Spillover Concrete overflow spillway weir

Location Left center section of embankment

SPILLWAY:

OVERFLOW

EMERGENCY

1898.0 (NGVD)

Elevation

Broad-crested weir

Type

49 feet

Width

Type of Control

Weir

Uncontrolled

--

Controlled

None

Type:

(Flashboards; gate)

One

Number

60 foot long weir

Size/Length

Concrete

Invert Material

Continuously

Anticipated Length  
of Operating Service

Unknown

Chute Length

12 feet

Height Between  
Spillway Crest  
& Approach Channel  
Invert (Weir Flow)

Type: \_\_\_\_\_

Location: \_\_\_\_\_

Records:

Date Unknown

Max. Reading Unknown

**FLOOD WATER CONTROL SYSTEM:**

Warning System None in effect

Method of Controlled Releases (mechanisms) Manually controlled slide gate to  
drain the impoundment

DRAINAGE AREA: 5,180 acres = 8.09 square miles

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type Rural, State Park

Terrain - Relief Relatively flat uplands (plateau)

Surface - Soil Glacial till

Runoff Potential (existing or planned extensive alterations to existing surface or subsurface conditions)

Primarily woodlands with scattered open fields; glacial till soils; average watershed slope is less than 5 percent

Potential Sedimentation problem areas (natural or man-made; present or future)

None

Potential Backwater problem areas for levels at maximum storage capacity including surcharge storage:

"Railroad grade road" on the southern edge of the reservoir

would be inundated

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the reservoir perimeter:


Location: Low reach ("railroad grade road") on southern edge of reservoir


Elevation: 1898.0 (NGVD)

Reservoir:

Length @ Maximum Pool 12,000 ± feet = 2.3 miles (Miles)

Length of Shoreline (@ Spillway Crest) 30,000 ± feet = 5.7 miles (Miles)





## WATERSHED MAP

WHETSTONE GULF STORAGE DAM  
INVENTORY No. NY 544

BLACK RIVER BASIN  
LEWIS COUNTY  
MARTINSBURG, NEW YORK



CALCULATIONS



## WATERSHED DATA FOR HEC-1 SNYDER HYDROGRAPH

### TIME TO PEAK

$$L = 39,000' = 5.68 \text{ miles}$$

$$L_c = 13,500' = 2.56 \text{ miles}$$

$$C_t = 2.2 \text{ for flat slopes}$$

$$T_p = C_t (L + L_c)^{0.3}$$

$$= 2.2 (5.68 + 2.56)^{0.3} = 4.91 \text{ Hours}$$

$$t_r = \frac{t_p}{5.5} = \frac{4.91}{5.5} = 0.89 \quad \text{USE } t_r = 0.5$$

$$t_{PR} = t_p + 0.25(t_r - t_p)$$

$$= 4.91 + 0.25(0.5 - 0.89)$$

$$= 4.81 \text{ Hours}$$

2)  $C_p = 0.63$  for HIGHLAND AREA

3) % IMPERVIOUS

$$\begin{aligned} \text{ROADS} & - 16,000 \text{ LF} \times 25' = 400,000 \text{ ft}^2 \\ \text{HOUSES} & - \pm 7 @ 1000 \text{ ft}^2 = \frac{7,000 \text{ ft}^2}{407,000 \text{ ft}^2} \end{aligned}$$

$$407,000 \text{ ft}^2 = 9.3 \text{ acres}$$

$$\frac{9.3 \text{ acres}}{5184 \text{ acres}} = 0.18 \%$$

4) WATERSHED AREA

$$5184 \text{ acres} / 640 = 8.10 \text{ Square Miles}$$

Based on 1" = 2000' USGS Map

PROJECT CORPS DAMS  
NY 544



FLAHERTY-GIAVARA ASSOCIATES  
ENVIRONMENTAL DESIGN CONSULTANTS  
ONE COLUMBUS PLAZA, NEW HAVEN, CONN 06510/203/788-1280

SHEET NO. 2 OF 4  
BY RAC DATE 4-16-81  
CHK'D. BY TLW DATE 4-21-81


5) RAINFALL DATA - (FROM HYDROMETEOROLOGICAL  
REPORT NO. 33)

24 Hour PMP = 18.6 inches for 200 square miles

<u>DURATION (HRS)</u>	<u>ADJ FACTOR %</u>
6	111
12	122
24	133
48	143



STAGE DISCHARGE DATA  
NTS



<u>STAGE</u>	<u><math>Q = (3.0) L H^{1.5}</math></u>	<u><math>Q = (2.5) L H^{1.5}</math></u>	<u>DISCHARGE</u>
1898.0	-		0
1899.0	3(60)(1) <sup>1.5</sup>		180.0
1900.0	3(60)(2) <sup>1.5</sup>		509.1
1900.6	3(60)(2.6) <sup>1.5</sup>		754.6
1901.0	3(60)(3) <sup>1.5</sup>	2.5(5)(4) <sup>1.5</sup>	938.5
1901.8	3(60)(3.8) <sup>1.5</sup>	2.5(5)(4.4) <sup>1.5</sup>	1349.5
1902.0	3(60)(4) <sup>1.5</sup>	2.5(5)(4.4) <sup>1.5</sup> 2.5(10)(2) <sup>1.5</sup>	1462.9
1902.3	3(60)(4.3) <sup>1.5</sup>	2.5(5)(4.7) <sup>1.5</sup> 2.5(10)(2.5) <sup>1.5</sup>	1641.5
1902.7	3(60)(4.7) <sup>1.5</sup>	2.5(5)(5.1) <sup>1.5</sup> 2.5(10)(2.9) <sup>1.5</sup> 2.5(15)(A) <sup>1.5</sup>	1903.0
1903.0	3(60)(5) <sup>1.5</sup>	2.5(5)(5.4) <sup>1.5</sup> 2.5(10)(3.2) <sup>1.5</sup> 2.5(15)(7) <sup>1.5</sup>	2113.8
1903.1	3(60)(5.1) <sup>1.5</sup>	2.5(5)(5.4) <sup>1.5</sup> 2.5(10)(3.3) <sup>1.5</sup> 2.5(15)(8) <sup>1.5</sup>	2186.4
1904.0	3(60)(6) <sup>1.5</sup> 3(3)(9) <sup>1.5</sup>	2.5(5)(6.4) <sup>1.5</sup> 2.5(10)(3.2) <sup>1.5</sup> 2.5(15)(1.7) <sup>1.5</sup> 2.5(240)(.9) <sup>1.5</sup>	3408.5
1905.0	3(60)(7) <sup>1.5</sup> 3(3)(11) <sup>1.5</sup>	2.5(5)(7.4) <sup>1.5</sup> 2.5(10)(3.2) <sup>1.5</sup> 2.5(15)(2.7) <sup>1.5</sup> 2.5(240)(1.9) <sup>1.5</sup>	5353.4


PROJECT CoEPS Vane  
NY 544



**FLAHERTY-GIAVARA ASSOCIATES**  
ENVIRONMENTAL DESIGN CONSULTANTS  
ONE COLUMBUS PLAZA, NEW HAVEN, CONN. 06510/203/780-1200

SHEET NO. 4 OF 4  
BY RAC DATE 4-20-81  
CHK'D. BY TLW DATE 4-21-81

STAGE DISCHARGE  
Spillway & Overflow SECTIONS



HEC-1 FLOOD HYDROGRAPH COMPUTATIONS

FLAHERTY GIOVARA ASSOCIATES, P. C.  
FLOOD HYDROGRAPH PACKAGE (HEC-1)  
DAM SAFETY VERSION JULY 1978  
LAST MODIFICATION 26 FEB 79

A1 NATIONAL DAM INSPECTION PROGRAM, PHASE I REPORT, CORPS OF ENGINEERS - NEW YORK DISTRICT  
A2 DAM INVENTORY NO. NY 544, WHEATSTONE GULF STORAGE DAM, LEWIS COUNTY, NEW YORK, APRIL 20, 1981  
A3 PREPARED BY FLAHERTY GIOVARA ASSOCIATES, P. C., ONE COLUMBUS PLAZA, NEW HAVEN, CONNECTICUT

B1 120  
B2 120  
B3 120  
B4 120  
B5 120  
B6 120  
B7 120  
B8 120  
B9 120  
B10 120  
B11 120  
B12 120  
B13 120  
B14 120  
B15 120  
B16 120  
B17 120  
B18 120  
B19 120  
B20 120  
B21 120  
B22 120  
B23 120  
B24 120  
B25 120  
B26 120  
B27 120

K1 INFLOW HYDROGRAPH - SNYDER METHOD  
K2 RESERVOIR ROUTING - MODIFIED PLUS METHOD

Y1 1897.0 1700.0 1507.0 1307.0 1107.0 907.0 707.0 507.0 307.0 107.0  
Y2 1903.0 1703.0 1503.0 1303.0 1103.0 903.0 703.0 503.0 303.0 103.0  
Y3 1909.0 1709.0 1509.0 1309.0 1109.0 909.0 709.0 509.0 309.0 109.0  
Y4 1915.0 1715.0 1515.0 1315.0 1115.0 915.0 715.0 515.0 315.0 115.0  
Y5 1921.0 1721.0 1521.0 1321.0 1121.0 921.0 721.0 521.0 321.0 121.0  
Y6 1927.0 1727.0 1527.0 1327.0 1127.0 927.0 727.0 527.0 327.0 127.0  
Y7 1933.0 1733.0 1533.0 1333.0 1133.0 933.0 733.0 533.0 333.0 133.0  
Y8 1939.0 1739.0 1539.0 1339.0 1139.0 939.0 739.0 539.0 339.0 139.0  
Y9 1945.0 1745.0 1545.0 1345.0 1145.0 945.0 745.0 545.0 345.0 145.0  
Y10 1951.0 1751.0 1551.0 1351.0 1151.0 951.0 751.0 551.0 351.0 151.0  
Y11 1957.0 1757.0 1557.0 1357.0 1157.0 957.0 757.0 557.0 357.0 157.0  
Y12 1963.0 1763.0 1563.0 1363.0 1163.0 963.0 763.0 563.0 363.0 163.0  
Y13 1969.0 1769.0 1569.0 1369.0 1169.0 969.0 769.0 569.0 369.0 169.0  
Y14 1975.0 1775.0 1575.0 1375.0 1175.0 975.0 775.0 575.0 375.0 175.0  
Y15 1981.0 1781.0 1581.0 1381.0 1181.0 981.0 781.0 581.0 381.0 181.0  
Y16 1987.0 1787.0 1587.0 1387.0 1187.0 987.0 787.0 587.0 387.0 187.0  
Y17 1993.0 1793.0 1593.0 1393.0 1193.0 993.0 793.0 593.0 393.0 193.0  
Y18 1999.0 1799.0 1599.0 1399.0 1199.0 999.0 799.0 599.0 399.0 199.0  
Y19 2005.0 1805.0 1605.0 1405.0 1205.0 1005.0 805.0 605.0 405.0 205.0  
Y20 2011.0 1811.0 1611.0 1411.0 1211.0 1011.0 811.0 611.0 411.0 211.0  
Y21 2017.0 1817.0 1617.0 1417.0 1217.0 1017.0 817.0 617.0 417.0 217.0  
Y22 2023.0 1823.0 1623.0 1423.0 1223.0 1023.0 823.0 623.0 423.0 223.0  
Y23 2029.0 1829.0 1629.0 1429.0 1229.0 1029.0 829.0 629.0 429.0 229.0  
Y24 2035.0 1835.0 1635.0 1435.0 1235.0 1035.0 835.0 635.0 435.0 235.0  
Y25 2041.0 1841.0 1641.0 1441.0 1241.0 1041.0 841.0 641.0 441.0 241.0  
Y26 2047.0 1847.0 1647.0 1447.0 1247.0 1047.0 847.0 647.0 447.0 247.0  
Y27 2053.0 1853.0 1653.0 1453.0 1253.0 1053.0 853.0 653.0 453.0 253.0

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS  
RUNDOWN HYDROGRAPH AT  
ROUTE HYDROGRAPH TO  
END OF NETWORK

\*\*\*\*\*  
FLOOD HYDROGRAPH PACKAGE (HEC-1)  
DAM SAFETY VERSION JULY 1978  
LAST MODIFICATION 26 FEB 79  
\*\*\*\*\*

RUN DATE: 8/20/  
TIME: 2:53 PM

NATIONAL DAM INSPECTION PROGRAM, PHASE I REPORT, CORPS OF ENGINEERS - NEW YORK DISTRICT  
DAM INVENTORY NO. NY 544, WHEATSTONE GULF STORAGE DAM, LEWIS COUNTY, NEW YORK, APRIL 20, 1981  
PREPARED BY FLAHERTY GIOVARA ASSOCIATES, P. C., ONE COLUMBUS PLAZA, NEW HAVEN, CONNECTICUT

NG 120  
NHR 0  
NMN 30  
IDAY 0  
JOPER 0  
JOB SPECIFICATION  
IHR 0  
NHT 0  
LROFT 0  
METRC 0  
TRACE 0  
IPLT 2  
IPRT 0  
NSTAN 0

## MULTI-PLAN ANALYSES TO BE PERFORMED

RTIOS= 0.50 0.68 0.69 0.70 0.71 0.72 0.73 0.74 1.00  
 NPLAN= 1 NRTIO= 9 LRTIO= 1

\*\*\*\*\* SUB-AREA RUNOFF COMPUTATION \*\*\*\*\*

## INFLOW HYDROGRAPH - SNYDER METHOD

ISTAG 1 ICOMP 0 IIECON 0 IITAPE 0 JPLT 0 JFRT 0 INAME 1 ISTAGE 0 IAUTO 0

IMYDQ 1 IUNG 1 IAREA 8.09 IENAP 0.00 ITRSDA 8.09 ITRSC 0.00 ITRATIO 0.000 IISAME 1 ILOCAL 0

## HYDROGRAPH DATA

PRECIP DATA  
 SPTS 1 PMS 18.80 RS 111.00 R2 122.00 R3 133.00 R4 143.00 R5 0.00

TRSPC COMPUTED BY THE PROGRAM IS 0.800

LOSS DATA  
 LROPT 0 STRKR 0.00 DLTKR 0.00 RTIOL 1.00 ERAIN 0.00 STRKS 0.00 RTIOK 1.00 STRTL 1.00 CNSTL 0.10 ALSHR 0.00 RTIMP 0.00

UNIT HYDROGRAPH DATA  
 TP= 4.81 CP=0.63 NYA= 0

## RECESSION DATA

SIRTS= -2.00 GRCSN= 20.10 RTIOK= 1.00 INTERVALS  
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 10.86 AND R= 8.62

UNIT HYDROGRAPH 52 END-OF-PERIOD ORDINATES, LAG= 4.79 HOURS, CP= 0.63 VOL= 1.00  
 23. 84. 170 268 374 482 577 647 679 709  
 686 628 559 498 443 393 351 313 279 248  
 221 197 173 154 137 124 110 98 87 78  
 69 55 43 39 34 31 27 24 21 18  
 17 15 14 12 11 10 9 8 7 6

MO DA	HR	MIN	PERIOD	RAIN	EXCS	LOZS	END-OF-PERIOD FLOW	MO DA	HR	MIN	PERIOD	RAIN	EXCS	LOZS	END-OF-PERIOD FLOW	CONV	CONV
1	0	30	1	0.00	0.00	0.00	1.02	1	0	30	1	0.14	0.00	0.00	1.00	49	49
1	0	30	2	0.00	0.00	0.00	1.02	1	0	30	2	0.14	0.00	0.00	1.00	56	56
1	0	30	3	0.00	0.00	0.00	1.02	1	0	30	3	0.14	0.00	0.00	1.00	70	70
1	0	30	4	0.00	0.00	0.00	1.02	1	0	30	4	0.14	0.00	0.00	1.00	92	92
1	0	30	5	0.00	0.00	0.00	1.02	1	0	30	5	0.14	0.00	0.00	1.00	123	123
1	0	30	6	0.00	0.00	0.00	1.02	1	0	30	6	0.14	0.00	0.00	1.00	163	163
1	0	30	7	0.00	0.00	0.00	1.02	1	0	30	7	0.14	0.00	0.00	1.00	210	210
1	0	30	8	0.00	0.00	0.00	1.02	1	0	30	8	0.14	0.00	0.00	1.00	286	286
1	0	30	9	0.00	0.00	0.00	1.02	1	0	30	9	0.14	0.00	0.00	1.00	330	330
1	0	30	10	0.00	0.00	0.00	1.02	1	0	30	10	0.14	0.00	0.00	1.00	378	378
1	0	30	11	0.00	0.00	0.00	1.02	1	0	30	11	0.14	0.00	0.00	1.00	434	434
1	0	30	12	0.00	0.00	0.00	1.02	1	0	30	12	0.14	0.00	0.00	1.00	487	487







12 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100 101 102 103 104 105 106 107 108



FLAHERTY DIAVARA ASSOCIATES, P. C.

THOUS CU H  
AC-FT  
PM  
302.47  
5133  
6334

HYDROGRAPH AT STA									
1 FOR PLAN I, RTIO 3									
11	10	9	8	7	6	5	4	3	2
17	17	16	15	14	13	12	11	10	9
5	5	4	4	3	3	3	3	3	3
39	39	38	37	36	35	34	33	32	31
42	42	41	40	39	38	37	36	35	34
39	39	38	37	36	35	34	33	32	31
277	277	276	275	274	273	272	271	270	269
2183	2183	2182	2181	2180	2179	2178	2177	2176	2175
2199	2199	2198	2197	2196	2195	2194	2193	2192	2191
2701	2701	2700	2699	2698	2697	2696	2695	2694	2693

THOUS CU H  
AC-FT  
PM  
302.47  
5133  
6334

HYDROGRAPH AT STA									
1 FOR PLAN II, RTIO 4									
11	10	9	8	7	6	5	4	3	2
17	17	16	15	14	13	12	11	10	9
5	5	4	4	3	3	3	3	3	3
39	39	38	37	36	35	34	33	32	31
42	42	41	40	39	38	37	36	35	34
39	39	38	37	36	35	34	33	32	31
277	277	276	275	274	273	272	271	270	269
2183	2183	2182	2181	2180	2179	2178	2177	2176	2175
2199	2199	2198	2197	2196	2195	2194	2193	2192	2191
2701	2701	2700	2699	2698	2697	2696	2695	2694	2693

THOUS CU H  
AC-FT  
PM  
302.47  
5133  
6334

HYDROGRAPH AT STA									
1 FOR PLAN I, RTIO 5									
11	10	9	8	7	6	5	4	3	2
17	17	16	15	14	13	12	11	10	9
5	5	4	4	3	3	3	3	3	3
39	39	38	37	36	35	34	33	32	31
42	42	41	40	39	38	37	36	35	34
39	39	38	37	36	35	34	33	32	31
277	277	276	275	274	273	272	271	270	269
2183	2183	2182	2181	2180	2179	2178	2177	2176	2175
2199	2199	2198	2197	2196	2195	2194	2193	2192	2191
2701	2701	2700	2699	2698	2697	2696	2695	2694	2693

THOUS CU H  
AC-FT  
PM  
302.47  
5133  
6334

33.	40.	50.	66.	87.	116.	149.	187.	227.	268.
308.	345.	388.	508.	570.	734.	962.	1262.	1639.	2142.
2796.	3542.	4325.	5091.	5799.	6374.	6767.	6966.	6967.	6739.
6362.	5868.	5351.	4835.	4341.	3891.	3490.	3131.	2809.	2520.
2260.	2025.	1812.	1620.	1446.	1289.	1148.	1022.	910.	810.
721.	678.	651.	625.	600.	576.	553.	531.	510.	490.

CFB	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
INCHES	5956	2632	1081	129758
AC-FT	149	75	31	3674
THOUS CU H	173.95	12.11	12.43	12.43
	307.50	315.81	315.81	315.81
	5221	5342	5342	5342
	640.	640.	640.	640.

HYDROGRAPH AT STA 10 FOR PLAN 1, RTIO 6									
11	10	9	8	7	6	5	4	3	2
11	10	9	8	7	6	5	4	3	2
17	17	17	17	17	17	17	17	17	17
3	3	3	3	3	3	3	3	3	3
4	4	4	4	4	4	4	4	4	4
98	98	98	98	98	98	98	98	98	98
44	44	44	44	44	44	44	44	44	44
35	35	35	35	35	35	35	35	35	35
312	312	312	312	312	312	312	312	312	312
2835	2835	2835	2835	2835	2835	2835	2835	2835	2835
6452	6452	6452	6452	6452	6452	6452	6452	6452	6452
2292	2292	2292	2292	2292	2292	2292	2292	2292	2292
732	732	732	732	732	732	732	732	732	732

CFB	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
INCHES	6040	2649	1097	131586
AC-FT	171	76	31	3726
THOUS CU H	176.40	12.28	12.61	12.61
	311.83	320.26	320.26	320.26
	5294	5437	5437	5437
	6550	6707	6707	6707

HYDROGRAPH AT STA 10 FOR PLAN 1, RTIO 7									
11	10	9	8	7	6	5	4	3	2
11	10	9	8	7	6	5	4	3	2
18	18	18	18	18	18	18	18	18	18
5	5	5	5	5	5	5	5	5	5
4	4	4	4	4	4	4	4	4	4
99	99	99	99	99	99	99	99	99	99
45	45	45	45	45	45	45	45	45	45
317	317	317	317	317	317	317	317	317	317
2871	2871	2871	2871	2871	2871	2871	2871	2871	2871
4541	4541	4541	4541	4541	4541	4541	4541	4541	4541
2321	2321	2321	2321	2321	2321	2321	2321	2321	2321
742	742	742	742	742	742	742	742	742	742

CFB	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
INCHES	6124	2706	1112	133413
AC-FT	173	77	31	3778
THOUS CU H	178.85	12.49	12.78	12.78
	312.19	324.71	324.71	324.71
	5294	5437	5437	5437
	6550	6707	6707	6707

5513.  
6800.

100

8 5 4  
7 5 3  
2 7 9  
2 2 3 2  
7 0 4 5  
2 6 2 7  
8 4 5  
5 1 1

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
7252	4208	2743	1125	13524	13524
205	176	128	128	360	360
	174	128	128	530	530
	191	320	351	327	327
	130	320	351	558	558
3078	541	875	875	2293	2293
377	377	377	377	1511	1511

C-18

HYDROGRAPH AT STA 17  
19  
14  
10  
13  
12  
11  
10  
9  
8  
7  
6  
5  
4  
3  
2  
1

1 FOR PLAN 1, RTID 9  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100  
101  
102  
103  
104  
105  
106  
107  
108  
109  
110  
111  
112  
113  
114  
115  
116  
117  
118  
119  
120  
121  
122  
123  
124  
125  
126  
127  
128  
129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144  
145  
146  
147  
148  
149  
150  
151  
152  
153  
154  
155  
156  
157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
172  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195  
196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211  
212  
213  
214  
215  
216  
217  
218  
219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335  
336  
337  
338  
339  
340  
341  
342  
343  
344  
345  
346  
347  
348  
349  
350  
351  
352  
353  
354  
355  
356  
357  
358  
359  
360  
361  
362  
363  
364  
365  
366  
367  
368  
369  
370  
371  
372  
373  
374  
375  
376  
377  
378  
379  
380  
381  
382  
383  
384  
385  
386  
387  
388  
389  
390  
391  
392  
393  
394  
395  
396  
397  
398  
399  
400  
401  
402  
403  
404  
405  
406  
407  
408  
409  
410  
411  
412  
413  
414  
415  
416  
417  
418  
419  
420  
421  
422  
423  
424  
425  
426  
427  
428  
429  
430  
431  
432  
433  
434  
435  
436  
437  
438  
439  
440  
441  
442  
443  
444  
445  
446  
447  
448  
449  
450  
451  
452  
453  
454  
455  
456  
457  
458  
459  
460  
461  
462  
463  
464  
465  
466  
467  
468  
469  
470  
471  
472  
473  
474  
475  
476  
477  
478  
479  
480  
481  
482  
483  
484  
485  
486  
487  
488  
489  
490  
491  
492  
493  
494  
495  
496  
497  
498  
499  
500  
501  
502  
503  
504  
505  
506  
507  
508  
509  
510  
511  
512  
513  
514  
515  
516  
517  
518  
519  
520  
521  
522  
523  
524  
525  
526  
527  
528  
529  
530  
531  
532  
533  
534  
535  
536  
537  
538  
539  
540  
541  
542  
543  
544  
545  
546  
547  
548  
549  
550  
551  
552  
553  
554  
555  
556  
557  
558  
559  
560  
561  
562  
563  
564  
565  
566  
567  
568  
569  
570  
571  
572  
573  
574  
575  
576  
577  
578  
579  
580  
581  
582  
583  
584  
585  
586  
587  
588  
589  
590  
591  
592  
593  
594  
595  
596  
597  
598  
599  
600  
601  
602  
603  
604  
605  
606  
607  
608  
609  
610  
611  
612  
613  
614  
615  
616  
617  
618  
619  
620  
621  
622  
623  
624  
625  
626  
627  
628  
629  
630  
631  
632  
633  
634  
635  
636  
637  
638  
639  
640  
641  
642  
643  
644  
645  
646  
647  
648  
649  
650  
651  
652  
653  
654  
655  
656  
657  
658  
659  
660  
661  
662  
663  
664  
665  
666  
667  
668  
669  
670  
671  
672  
673  
674  
675  
676  
677  
678  
679  
680  
681  
682  
683  
684  
685  
686  
687  
688  
689  
690  
691  
692  
693  
694  
695  
696  
697  
698  
699  
700  
701  
702  
703  
704  
705  
706  
707  
708  
709  
710  
711  
712  
713  
714  
715  
716  
717  
718  
719  
720  
721  
722  
723  
724  
725  
726  
727  
728  
729  
730  
731  
732  
733  
734  
735  
736  
737  
738  
739  
740  
741  
742  
743  
744  
745  
746  
747  
748  
749  
750  
751  
752  
753  
754  
755  
756  
757  
758  
759  
760  
761  
762  
763  
764  
765  
766  
767  
768  
769  
770  
771  
772  
773  
774  
775  
776  
777  
778  
779  
780  
781  
782  
783  
784  
785  
786  
787  
788  
789  
790  
791  
792  
793  
794  
795  
796  
797  
798  
799  
800  
801  
802  
803  
804  
805  
806  
807  
808  
809  
810  
811  
812  
813  
814  
815  
816  
817  
818  
819  
820  
821  
822  
823  
824  
825  
826  
827  
828  
829  
830  
831  
8

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
9813	5897	3707	1923	18275	517
278	238	1703	43	517	21
	965	1708	1731	17481	214
	245	435	44	7532	7532
	460	4070	9315	7532	7532
	5131				4315

100

## HYDROGRAPH ROUTING

NO	MODIFIED	PLUS	METHOD	JPLT	JPR
ITAG	ICOMP	IECON	ITAPE		

NAME 1STAGE 1AUTO

1. The first part of the document is a list of names and titles, including "The Hon. Mr. Justice" and "The Hon. Mr. Justice".





PEAK OUTFLOW IS 110. AT TIME 52.00 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL
CFR	110	1076	59	227	2785
INCHES	131	130	18	6	773
MM		3.24	2.61	2.61	2.61
AC-FT		344	137	137	137
THOUS		558	137	137	137

**\*DVF\***

### NOTATION

INFLOW(I), OUTFLOW(Q) AND OBSERVED FLOW(\*)

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
000	100	200	300	400	500	600	700	800	900	1000	1100	1200	1300	1400	1500	1600	1700	1800	1900	2000	2100	2200	2300	2400	2500	2600	2700	2800	2900	3000
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30

311  
30 321  
15 00 331  
16 00 341  
17 00 351  
18 00 361  
19 00 371  
20 00 381  
21 00 391  
22 00 401  
23 00 411  
24 00 421  
25 00 431  
26 00 441  
27 00 451  
28 00 461  
29 00 471  
30 00 481  
31 00 491  
32 00 501  
33 00 511  
34 00 521  
35 00 531  
36 00 541  
37 00 551  
38 00 561  
39 00 571  
40 00 581  
41 00 591  
42 00 601  
43 00 611  
44 00 621  
45 00 631  
46 00 641  
47 00 651  
48 00 661  
49 00 671  
50 00 681  
51 00 691  
52 00 701  
53 00 711  
54 00 721  
55 00 731  
56 00 741  
57 00 751  
58 00 761  
59 00 771  
60 00 781  
61 00 791  
62 00 801  
63 00 811  
64 00 821  
65 00 831  
66 00 841  
67 00 851  
68 00 861  
69 00 871  
70 00 881



STATION 1, PLAN 1, RATIO 2  
END-OF-PERIOD HYDROGRAPH ORDINATES

[illegible]

[illegible][illegible]

PEAK OUTFLOW IS 2020 AT TIME 51 00 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CPB	2020	1941	1037	419	90237	
CPB	57	55	30	12	1423	
INCHES		2.23	4.81	4.81	4.81	
MM		26.68	122.27	122.27	122.27	
AC-FT		3076	3076	3076	3076	
INCHES		1.87	3.51	3.51	3.51	

**\* QVF \***

[illegible]





[illegible]

STAGE	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100															
1	886	887	888	889	890	891	892	893	894	895	896	897	898	899	900	901	902	903	904	905	906	907	908	909	910	911	912	913	914	915	916	917	918	919	920	921	922	923	924	925	926	927	928	929	930	931	932	933	934	935	936	937	938	939	940	941	942	943	944	945	946	947	948	949	950	951	952	953	954	955	956	957	958	959	960	961	962	963	964	965	966	967	968	969	970	971	972	973	974	975	976	977	978	979	980	981	982	983	984	985	986	987	988	989	990	991	992	993	994	995	996	997	998	999	1000

PEAK OUTFLOW IS 2076. AT TIME 51.00 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CFR	2079	1973	1075	430	51602	
CMS	59	56	30	12	1461	
INCHES	2.27	2.24	1.54	1.14	4.74	
MM	58.21	56.89	39.37	29.27	125.59	
AC FT	1219	988	1212	232	3132	
THOUS	2630		2630		2630	

# DVF #

STATION

```
INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(*)
3000.      4000.      5000.      6000.
```

0-NNNNN  
0-NNNNN  
0-NNNNN





8 6301  
9 6401  
10 6501  
11 6601  
12 6701  
13 6801  
14 6901  
15 7001  
16 7101  
17 7201  
18 7301  
19 7401  
20 7501  
21 7601  
22 7701  
23 7801  
24 7901  
25 8001  
26 8101  
27 8201  
28 8301  
29 8401  
30 8501  
31 8601  
32 8701  
33 8801  
34 8901  
35 9001  
36 9101  
37 9201  
38 9301  
39 9401  
40 9501  
41 9601  
42 9701  
43 9801  
44 9901  
50 0001  
51 0101  
52 0201  
53 0301  
54 0401  
55 0501  
56 0601  
57 0701  
58 0801  
59 0901  
60 1001  
61 1101  
62 1201  
63 1301  
64 1401  
65 1501  
66 1601  
67 1701  
68 1801  
69 1901  
70 2001  
71 2101  
72 2201  
73 2301  
74 2401  
75 2501  
76 2601  
77 2701  
78 2801  
79 2901  
80 3001  
81 3101  
82 3201  
83 3301  
84 3401  
85 3501  
86 3601  
87 3701  
88 3801  
89 3901  
90 4001  
91 4101  
92 4201  
93 4301  
94 4401  
95 4501  
96 4601  
97 4701  
98 4801  
99 4901  
100 5001  
101 5101  
102 5201  
103 5301  
104 5401  
105 5501  
106 5601  
107 5701  
108 5801  
109 5901  
110 6001  
111 6101  
112 6201  
113 6301  
114 6401  
115 6501  
116 6601  
117 6701  
118 6801  
119 6901  
120 7001



\*QVF\*

STATION 1

INFLW(1), 3000.	OUTFLOW(2), 4000.	AND OBSERVED FLOW(3), 5000.	7000.	0.	0.	0.	0.	0.	0.
01121	000000	01121							
01122	000000	01122							
01123	000000	01123							
01124	000000	01124							
01125	000000	01125							
01126	000000	01126							
01127	000000	01127							
01128	000000	01128							
01129	000000	01129							
01130	000000	01130							
01131	000000	01131							
01132	000000	01132							
01133	000000	01133							
01134	000000	01134							
01135	000000	01135							
01136	000000	01136							
01137	000000	01137							
01138	000000	01138							
01139	000000	01139							
01140	000000	01140							
01141	000000	01141							
01142	000000	01142							
01143	000000	01143							
01144	000000	01144							
01145	000000	01145							
01146	000000	01146							
01147	000000	01147							
01148	000000	01148							
01149	000000	01149							
01150	000000	01150							
01151	000000	01151							
01152	000000	01152							
01153	000000	01153							
01154	000000	01154							
01155	000000	01155							
01156	000000	01156							
01157	000000	01157							
01158	000000	01158							
01159	000000	01159							
01160	000000	01160							
01161	000000	01161							
01162	000000	01162							
01163	000000	01163							
01164	000000	01164							
01165	000000	01165							
01166	000000	01166							
01167	000000	01167							
01168	000000	01168							
01169	000000	01169							
01170	000000	01170							
01171	000000	01171							
01172	000000	01172							
01173	000000	01173							
01174	000000	01174							
01175	000000	01175							
01176	000000	01176							
01177	000000	01177							
01178	000000	01178							
01179	000000	01179							
01180	000000	01180							
01181	000000	01181							
01182	000000	01182							
01183	000000	01183							
01184	000000	01184							
01185	000000	01185							
01186	000000	01186							
01187	000000	01187							
01188	000000	01188							
01189	000000	01189							
01190	000000	01190							
01191	000000	01191							
01192	000000	01192							
01193	000000	01193							
01194	000000	01194							
01195	000000	01195							
01196	000000	01196							
01197	000000	01197							
01198	000000	01198							
01199	000000	01199							
01200	000000	01200							
01201	000000	01201							
01202	000000	01202							
01203	000000	01203							
01204	000000	01204							
01205	000000	01205							
01206	000000	01206							
01207	000000	01207							
01208	000000	01208							
01209	000000	01209							
01210	000000	01210							
01211	000000	01211							
01212	000000	01212							
01213	000000	01213							
01214	000000	01214							
01215	000000	01215							
01216	000000	01216							
01217	000000	01217							
01218	000000	01218							
01219	000000	01219							
01220	000000	01220							
01221	000000	01221							
01222	000000	01222							
01223	000000	01223							
01224	000000	01224							
01225	000000	01225							
01226	000000	01226							
01227	000000	01227							
01228	000000	01228							
01229	000000	01229							
01230	000000	01230							
01231	000000	01231							
01232	000000	01232							
01233	000000	01233							
01234	000000	01234							
01235	000000	01235							
01236	000000	01236							
01237	000000	01237							
01238	000000	01238							
01239	000000	01239							
01240	000000	01240							
01241	000000	01241							
01242	000000	01242							
01243	000000	01243							
01244	000000	01244							
01245	000000	01245							
01246	000000	01246							
01247	000000	01247							
01248	000000	01248							
01249	000000	01249							
01250	000000	01250							
01251	000000	01251							
01252	000000	01252							
01253	000000	01253							
01254	000000	01254							
01255	000000	01255							
01256	000000	01256							
01257	000000	01257							
01258	000000	01258							
01259	000000	01259							
01260	000000	01260							
01261	000000	01261							
01262	000000	01262							
01263	000000	01263							
01264	000000	01264							
01265	000000	01265							
01266	000000	01266							
01267	000000	01267							
01268	000000	01268							
01269	000000	01269							
01270	000000	01270							
01271	000000	01271							
01272	000000	01272							
01273	000000	01273							
01274	000000	01274							
01275	000000	01275							
01276	000000	01276							
01277	000000	01277							
01278	000000	01278							
01279	000000	01279							
01280	000000	01280							
01281	000000	01281							
01282	000000	01282							
01283	000000	01283							
01284	000000	01284							
01285	000000	01285							
01286	000000	01286							
01287	000000	01287							
01288	000000	01288							
01289	000000	01289							
01290	000000	01290							
01291	000000	01291							
01292	000000	01292							
01293	000000	01293							
01294	000000	01294							
01295	000000	01295							
01296	000000	01296							
01297	000000	01297							
01298	000000	01298							
01299	000000	01299							
01300	000000	01300							
01301	000000	01301							
01302	000000	01302							
01303	000000	01303							
01304	000000	01304							
01305	000000	01305							
01306	000000	01306							
01307	000000	01307							
01308	000000	01308							
01309	000000	01309							

231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310

STATION 1, PLAN 1, RATIO 5  
END-OF-PERIOD HYDROGRAPH ORDINATES

C-32

Year	1903.1	1903.2	1903.3	1903.4	1903.5	1903.6	1903.7	1903.8	1903.9	1904.0	1904.1	1904.2	1904.3	1904.4	1904.5	1904.6	1904.7	1904.8	1904.9	1905.0	1905.1	1905.2	1905.3	1905.4	1905.5	1905.6	1905.7	1905.8	1905.9	1906.0	1906.1	1906.2	1906.3	1906.4	1906.5	1906.6	1906.7	1906.8	1906.9	1907.0	1907.1	1907.2	1907.3	1907.4	1907.5	1907.6	1907.7	1907.8	1907.9	1908.0	1908.1	1908.2	1908.3	1908.4	1908.5	1908.6	1908.7	1908.8	1908.9	1909.0	1909.1	1909.2	1909.3	1909.4	1909.5	1909.6	1909.7	1909.8	1909.9	1910.0	1910.1	1910.2	1910.3	1910.4	1910.5	1910.6	1910.7	1910.8	1910.9	1911.0	1911.1	1911.2	1911.3	1911.4	1911.5	1911.6	1911.7	1911.8	1911.9	1912.0	1912.1	1912.2	1912.3	1912.4	1912.5	1912.6	1912.7	1912.8	1912.9	1913.0	1913.1	1913.2	1913.3	1913.4	1913.5	1913.6	1913.7	1913.8	1913.9	1914.0	1914.1	1914.2	1914.3	1914.4	1914.5	1914.6	1914.7	1914.8	1914.9	1915.0	1915.1	1915.2	1915.3	1915.4	1915.5	1915.6	1915.7	1915.8	1915.9	1916.0	1916.1	1916.2	1916.3	1916.4	1916.5	1916.6	1916.7	1916.8	1916.9	1917.0	1917.1	1917.2	1917.3	1917.4	1917.5	1917.6	1917.7	1917.8	1917.9	1918.0	1918.1	1918.2	1918.3	1918.4	1918.5	1918.6	1918.7	1918.8	1918.9	1919.0	1919.1	1919.2	1919.3	1919.4	1919.5	1919.6	1919.7	1919.8	1919.9	1920.0	1920.1	1920.2	1920.3	1920.4	1920.5	1920.6	1920.7	1920.8	1920.9	1921.0	1921.1	1921.2	1921.3	1921.4	1921.5	1921.6	1921.7	1921.8	1921.9	1922.0	1922.1	1922.2	1922.3	1922.4	1922.5	1922.6	1922.7	1922.8	1922.9	1923.0	1923.1	1923.2	1923.3	1923.4	1923.5	1923.6	1923.7	1923.8	1923.9	1924.0	1924.1	1924.2	1924.3	1924.4	1924.5	1924.6	1924.7	1924.8	1924.9	1925.0	1925.1	1925.2	1925.3	1925.4	1925.5	1925.6	1925.7	1925.8	1925.9	1926.0	1926.1	1926.2	1926.3	1926.4	1926.5	1926.6	1926.7	1926.8	1926.9	1927.0	1927.1	1927.2	1927.3	1927.4	1927.5	1927.6	1927.7	1927.8	1927.9	1928.0	1928.1	1928.2	1928.3	1928.4	1928.5	1928.6	1928.7	1928.8	1928.9	1929.0	1929.1	1929.2	1929.3	1929.4	1929.5	1929.6	1929.7	1929.8	1929.9	1930.0	1930.1	1930.2	1930.3	1930.4	1930.5	1930.6	1930.7	1930.8	1930.9	1931.0	1931.1	1931.2	1931.3	1931.4	1931.5	1931.6	1931.7	1931.8	1931.9	1932.0	1932.1	1932.2	1932.3	1932.4	1932.5	1932.6	1932.7	1932.8	1932.9	1933.0	1933.1	1933.2	1933.3	1933.4	1933.5	1933.6	1933.7	1933.8	1933.9	1934.0	1934.1	1934.2	1934.3	1934.4	1934.5	1934.6	1934.7	1934.8	1934.9	1935.0	1935.1	1935.2	1935.3	1935.4	1935.5	1935.6	1935.7	1935.8	1935.9	1936.0	1936.1	1936.2	1936.3	1936.4	1936.5	1936.6	1936.7	1936.8	1936.9	1937.0</
------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	----------

PEAK OUTFLOW IS 2190. AT TIME 50.50 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CFB	2190.	2101.	1322.	459.	5438.	5438.
CLS	62.	54.	54.	54.	157.	157.
INCUB		2.42	2.81	3.81	5.21	5.21
ACFT		41.37	1322.8	1322.8	2770.	1322.8
THOUS CU M		1042.	2246.	2246.	2770.	2770.

**#DVF#**

STATION 11


	INFLUX(I),	OUTFLOW(O) AND	OBSERVED FLOW(O)	
0.	1000.	2000.	3000.	4000.
				5000.
				6000.
				7000.
				8000.
				9000.
				10000.

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100

**PAGE 0023**

**FLAHERTY O'AVARA ASSOCIATES, P. C.**

[illegible]



#DIV#

STATION 1, PLAN 1, RATIO 6  
END-OF-PERIOD HYDROGRAPH ORDINATES

[illegible]



PEAK OUTFLOW IS 2265. AT TIME 90.50 HOURS

**END**

[illegible]

14 30 301  
 15 30 311  
 16 30 321  
 17 30 331  
 18 30 341  
 19 30 351  
 20 30 361  
 21 30 371  
 22 30 381  
 23 30 391  
 24 30 401  
 25 30 411  
 26 30 421  
 27 30 431  
 28 30 441  
 29 30 451  
 30 30 461  
 31 30 471  
 32 30 481  
 33 30 491  
 34 30 501  
 35 30 511  
 36 30 521  
 37 30 531  
 38 30 541  
 39 30 551  
 40 30 561  
 41 30 571  
 42 30 581  
 43 30 591  
 44 30 601  
 45 30 611  
 46 30 621  
 47 30 631  
 48 30 641  
 49 30 651  
 50 30 661  
 51 30 671  
 52 30 681  
 53 30 691  
 54 30 701  
 55 30 711  
 56 30 721  
 57 30 731  
 58 30 741  
 59 30 751  
 60 30 761  
 61 30 771  
 62 30 781  
 63 30 791  
 64 30 801  
 65 30 811  
 66 30 821  
 67 30 831  
 68 30 841  
 69 30 851  
 70 30 861

AD-A109 798

FLAHERTY-GIAVARA ASSOCIATES NEW HAVEN CT

F/G 13/13

NATIONAL DAM SAFETY PROGRAM. WHETSTONE GULF STORAGE DAM (INVENT--ETC(U)


JUL 81 H C FLAHERTY

DACW51-81-C-0006

NI

UNCLASSIFIED


2 of 2  
AD-A  
100 798




2 OF 2

AD A

109798





**#DYN#**

STATION 1, PLAN 1, RATIO 7  
END-OF-PERIOD HYDROGRAPH ORDINATES

OUTFLOW		STORAGE	
0000000000	1071	0000000000	1304
0000000000	2345	0000000000	2331
0000000000	1840	0000000000	1777
0000000000	1520	0000000000	1718
0000000000	2195	0000000000	2250
0000000000	2278	0000000000	1655
0000000000	1601	0000000000	1715
0000000000	1886	0000000000	1520
0000000000	2037	0000000000	1718
0000000000	2134	0000000000	2250
0000000000	2089	0000000000	1655
0000000000	1500	0000000000	1715
0000000000	1434	0000000000	1520
0000000000	2219	0000000000	1718
0000000000	2231	0000000000	2250
0000000000	1452	0000000000	1655
0000000000	2292	0000000000	1715
0000000000	1768	0000000000	1520
0000000000	1407	0000000000	1718
0000000000	2333	0000000000	2250
0000000000	1361	0000000000	1655

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528	529	530	531	532	533	534	535	536	537	538	539	540	541	542	543	544	545	546	547	548	549	550	551	552	553	554	555	556	557	558	559	560	561	562	563	564	565	566	567	568	569	570	571	572	573	574	575	576	577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592	593	594	595	596	597	598	599	600	601	602	603	604	605	606	607	608	609	610	611	612	613	614	615	616	617	618	619	620	621	622	623	624	625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640	641	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656	657	658	659	660	661	662	663	664	665	666	667	668	669	670	671	672	673	674	675	676	677	678	679	680	681	682	683	684	685	686	687	688	689	690	691	692	693	694	695	696	697	698	699	700	701	702	703	704	705	706	707	708	709	710	711	712	713	714	715	716	717	718	719	720	721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736	737	738	739	740	741	742	743	744	745	746	747	748	749	750	751	752	753	754	755	756	757	758	759	760	761	762	763	764	765	766	767	768	769	770	771	772	773	774	775	776	777	778	779	780	781	782	783	784	785	786	787	788	789	790	791	792	793	794	795	796	797	798	799	800	801	802	803	804	805	806	807	808	809	810	811	812	813	814	815	816	817	818	819	820	821	822	823	824	825	826	827	828	829	830	831	832	833	834	835	836	837	838	839	840	841	842	843	844	845	846	847	848	849	850	851	852	853	854	855	856	857	858	859	860	861	862	863	864	865	866	867	868	869	870	871	872	873	874	875	876	877	878	879	880	881	882	883	884	885	886	887	888	889	890	891	892	893	894	895	896	897	898	899	900	901	902	903	904	905	906	907	908	909	910	911	912	913	914	915	916	917	918	919	920	921	922	923	924	925	926	927	928	929	930	931	932	933	934	935	936	937	938	939	940	941	942	943	944	945	946	947	948	949	950	951	952	953	954	955	956	957	958	959	960	961	962	963	964	965	966	967	968	969	970	971	972	973	974	975	976	977	978	979	980	981	982	983	984	985	986	987	988	989	990	991	992	993	994	995	996	997	998	999	1000	1001	1002	1003	1004	1005	1006	1007	1008	1009	1010	1011	1012	1013	1014	1015	1016	1017	1018	1019	1020	1021	1022	1023	1024	1025	1026	1027	1028	1029	1030	1031	1032	1033	1034	1035	1036	1037	1038	1039	1040	1041	1042	1043	1044	1045	1046	1047	1048	1049	1050	1051	1052	1053	1054	1055	1056	1057	1058	1059	1060	1061	1062	1063	1064	1065	1066	1067	1068	1069	1070	1071	1072	1073	1074	1075	1076	1077	1078	1079	1080	1081	1082	1083	1084	1085	1086	1087	1088	1089	1090	1091	1092	1093	1094	1095	1096	1097	1098	1099	1100	1101	1102	1103	1104	1105	1106	1107	1108	1109	1110	1111	1112	1113	1114	1115	1116	1117	1118	1119	1120	1121	1122	1123	1124	1125	1126	1127	1128	1129	1130	1131	1132	1133	1134	1135	1136	1137	1138	1139	1140	1141	1142	1143	1144	1145	1146	1147	1148	1149	1150	1151	1152	1153	1154	1155	1156	1157	1158	1159	1160	1161	1162	1163	1164	1165	1166	1167	1168	1169	1170	1171	1172	1173	1174	1175	1176	1177	1178	1179	1180	1181	1182	1183	1184	1185	1186	1187	1188	1189	1190	1191	1192	1193	1194	1195	1196	1197	1198	1199	1200	1201	1202	1203	1204	1205	1206	1207	1208	1209	1210	1211	1212	1213	1214	1215	1216	1217	1218	1219	1220	1221	1222	1223	1224	1225	1226	1227	1228	1229	1230	1231	1232	1233	1234	1235	1236	1237	1238	1239	1240	1241	1242	1243	1244	1245	1246	1247	1248	1249	1250	1251	1252	1253	1254	1255	1256	1257	1258	1259	1260	1261	1262	1263	1264	1265	1266	1267	1268	1269	1270	1271	1272	1273	1274	1275	1276	1277	1278	1279	1280	1281	1282	1283	1284	1285	1286	1287	1288	1289	1290	1291	1292	1293	1294	1295	1296	1297	1298	1299	1300	1301	1302	1303	1304	1305	1306	1307	1308	1309	1310	1311	1312	1313	1314	1315	1316	1317	1318	1319	1320	1321	1322	1323	1324	1325	1326	1327	1328	1329	1330	1331	1332	1333	1334	1335	1336	1337	1338	1339	1340	1341	1342	1343	1344	1345	1346	1347	1348	1349	1350	1351	1352	1353	1354	1355	1356	1357	1358	1359	1360	1361	1362	1363	1364	1365	1366	1367	1368	1369	1370	1371	1372	1373	1374	1375	1376	1377	1378	1379	1380	1381	1382	1383	1384	1385	1386	1387	1388	1389	1390	1391	1392	1393	1394	1395	1396	1397	1398	1399	1400	1401	1402	1403	1404	1405	1406	1407	1408	1409	1410	1411	1412	1413	1414	1415	1416	1417	1418	1419	1420	1421	1422	1423	1424	1425	1426	1427	1428	1429	1430	1431	1432	1433	1434	1435	1436	1437	1438	1439	1440	1441	1442	1443	1444	1445	1446	1447	1448	1449	1450	1451	1452	1453	1454	1455	1456	1457	1458	1459	1460	1461	1462	1463	1464	1465	1466	1467	1468	1469	1470	1471	1472	1473	1474	1475	1476	1477	1478	1479	1480	1481	1482	1483	1484</
---	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	--------

171 181 191 201 211 221 231 241 251 261 271 281 291 301 311 321 331 341 351 361 371 381 391 401 411 421 431 441 451 461 471 481 491 501 511 521 531 541 551 561 571 581 591 601 611 621 631 641 651 661 671 681 691 701 711 721 731 741 751 761 771 781 791 801 811 821 831 841 851 861 871 881 891 901 911 921 931 941 951 961 971 981 991







51 41 71 81 101 111 121 131 141 151 161 171 181 191 201 211 221 231 241 251 261 271 281 291 301 311 321 331 341 351 361 371 381 391 401 411 421 431 441 451 461 471 481 491 501 511 521 531 541 551 561 571 581 591 601 611 621 631 641 651 661 671 681 691 701 711 721 731 741 751 761 771 781 791 801 811 821 831 841 851 861 871 881 891 901 911 921 931 941 951 961 971 981 991

**PAGE 0035.**

[illegible]





1223334455667789101112131415161718192021222324252627282930313233343536373839404142434445464748495051525354555657585960616263646566676869707172737475767778798081828384858687888990919293949596979899100101102103104105106



FLAHERTY GIOVARA ASSOCIATES, P.C.

PAGE 0040

\*\*\*\*\*1.00\*\*\*\*\*1904.77\*\*\*\*\*4521\*\*\*\*\*4876\*\*\*\*\*11.00\*\*\*\*\*48.50\*\*\*\*\*0.00\*\*\*\*\*


FLOOD HYDROGRAPH PACKAGE (HEC-1)  
DAM SAFETY VERSION JULY 1978  
LAST MODIFICATION 26 FEB 79  
\*\*\*\*\*



APPENDIX D  
STRUCTURAL STABILITY ANALYSIS

Spillway Data: Exist. Dwg's as applicable

Peak flow (Spillway Crest + 5') El. 1903'  
Normal Summer Cond. \_\_\_\_\_  
Elev. 1899'



<u>Section</u>	<u>Wt.</u>	<u>Dist.</u>	<u>Mom. (Toe)</u>
(1) $.5 \times \frac{12}{2} \times .15 =$	$0.45^K$	$(3.5 + \frac{1.0}{3}) 3.84$	$1.73^{1K}$
(2) $\frac{11.917 \times 10.75}{2} \times .15 =$	$9.61^K$	$(4 + \frac{11.917}{3}) 7.97'$	$76.61^{1K}$
(3) $1.25 \times 12.417 \times .15 =$	$2.33^K$	$(3.5 + \frac{12.417}{2}) 9.71 =$	$22.62^{1K}$
(4) $1.5 \times 17.17 \times .15 =$	$3.86$	$\frac{17.17}{2}$	$= 33.17$
(5) $1.75 \times 4.5 \times .15 =$	$1.18^K$	$16.3'$	$= 19.23$
	<u><math>17.43^K</math></u>		<u><math>130.74^{1K}</math></u>



$$P_{Avent.} = 1' \times .0624 \times 16.05' = 1^K \quad \times (.707 \times 8.03 + .5) = 6.21^K$$

$$P_{Bvent} = .0624 \times \frac{16.05^2}{2} \times .707 = 5.68^K \quad \times (.707 \times 10.7') + .5 = 45.82^K$$

$$\Sigma V = 24.11$$

$$\Sigma M_R = 182.761^K$$

$$\Sigma F_{H2} = 1.25 \times .0624 \times 1.25 + 10.75 \times .0624 \times 1.25 = 0.94$$

$$\Sigma F_{Horiz} = .94 + 1^K + 5.68 = 7.62^K$$

$$\Sigma M_{O.T.} = 1^K (12 - (8.03 \cos 45)) + 5.68 \times (1.25 + 5.35 \sin 45) + .94 \times .625$$

$$= 6.32 + 28.55 + .59 = 35.491^K$$

$$Upl. ft = 12 \times .0624 \times \frac{13.67}{2} = 5.12^K \quad \times (13.67 \times .67) = 46.61^K$$

Using  $\frac{2}{3}$  U for Stability Comp.

$$\frac{2}{3} \times 5.12 \times \frac{2}{3} (13.67) = 31.11^K$$

$$e = \frac{182.76 - (35.5 + 31.11)}{24.11 - 5.12} = 6.12' \div 17.17 = .36b$$

$$F.S._{O.T.} = \frac{182.76}{35.5 + 31.11} = 2.74 \text{ O.K.}$$

$$F.S._{SL} = \frac{24.11 - 5.12}{7.62} = 2.49 \text{ O.K.}$$

Soil Press.  $e = \frac{17.17}{2} - 6.12 = 2.47$

$$P = \frac{24.11}{17.17} \left( 1 \pm \frac{2.47 \times 6}{17.17} \right) = \begin{pmatrix} 1.86 \\ .14 \end{pmatrix} = \frac{2.61 \text{ KSF}}{0.20 \text{ KSF}} \text{ Toe/Heel}$$

### Ice Load + Normal Load:

Horiz. Force  $5^K/ft.$  Ice at top of Spillway:

$$\Sigma F_H = 7.62 + 5 = 12.62^K \quad M_{OT} = 66.61 + 5 \times 12' = 126.61^K$$

$$F.S._{SL} = \frac{24.11 - 5.12}{12.62} = 1.50 \text{ (Low)} \quad F.S._{O.T.} = \frac{182.76}{126.61} = 1.44$$

D-2

(Less than desirable)



Max. Oper. Load. Top of water = to top of dam  
 5.1' above Crest of Spillway  
 $P = 5.1 \times .0624 = .318 \text{ K/SF}$

$$P_{AV} = P_{AH} = .318 \times 16.05' = 5.1 \text{ K} \times (6.17 + 3.5) = 49.32 \text{ 'K}$$

$$P_D = 5.68 \times (8.63 + 3.5) = 68.90 \text{ 'K}$$

$$\Sigma P_V = .45 + 9.61 + 2.33 + 3.86 + 1.18 + 5.1 + 5.68 = 28.21 \text{ K}$$

$$\Sigma P_H = 5.68 + 5.1 = 10.78 \text{ K}$$

$$\Sigma M_R = 130.74 + 49.32 + 68.9 = 248.96 \text{ 'K}$$

$$\Sigma M_{OT} = 5.1 \times 6.93' + 5.68 \times 5.03 + 31.11 = 95.04 \text{ 'K}$$

$$\text{Loc. of Res. } \frac{248.96 - 95.04}{(28.21 - 5.12)} = 6.67 \div 17.17 = \underline{\underline{.39}}$$

$$e = \frac{17.17}{2} - 6.67 = 1.92 \quad P = \frac{28.21}{17.17} \left( 1 \pm \frac{6 \times 1.92}{17.17} \right) = \left( \frac{1.67}{+.33} \right)$$

$$\text{S.P. } \Sigma \text{ Toe } 2.74 \text{ K/SF}$$

$$\text{Heel } 0.54 \text{ K/SF}$$

Reinf. Conc. Section Adequate. for Soil Press.

$$F.S.O.T. = \frac{248.96}{95.04} = \underline{\underline{2.62}} \text{ OK}$$

$$F.S.SL = \frac{(28.21 - 5.12)}{10.78} = \underline{\underline{2.14}} \text{ OK}$$



P.M.F.

6.8' above crest of spillway

$$P = 6.8 \times .0624 = 0.424 \text{ K/ft}$$

$$P_{AV} = .424 \times 16.05 = 6.81 \text{ K} \times 9.67' = 65.85 \text{ K}$$

$$P_B = 5.68 \times 12.13 = 68.90 \text{ K}$$

$$\Sigma P_V = 28.21 + (6.81 - 5.12) = 29.92 \text{ K}$$

$$\Sigma P_H = 6.81 + 5.68 = 12.49 \text{ K}$$

$$\Sigma M_R = 130.79 + 65.85 + 68.9 = 265.49$$

$$\Sigma M_{O.T.} = 6.81 \times 6.93 + 5.68 \times 5.03' = 75.8 \text{ K}$$

$$F.S.O.T. = \frac{265.49}{(75.8 + 31.11)} = 2.48 \text{ O.K.}$$

$$F.S.SL = \frac{29.92 - 5.12}{12.49} = 1.99 \text{ O.K. w/ add'l resistance to sliding provided by shear key.}$$

$$\text{Loc. of Res. : } \frac{265.49 - 106.91}{(29.92 - 5.12)} = 6.39' + 17.17' = 0.37 \text{ b}$$

$$S.P. \& e = \frac{17.17}{2} - 6.39 = 2.20 \quad S.P. = \frac{29.92}{17.17} \left( 1 \pm \frac{6 \times 2.2}{17.17} \right) \frac{1.76}{.24}$$

$$Toe = 3.07 \text{ K/5F}$$

$$Heel = 0.42 \text{ K/5F}$$

Add'l Mom. due to inertial effects of dam & H<sub>2</sub>O

(Horiz. accel. effects of 0.1 G on Mass of Dam)

$$1.5 \times 17.17 \times .15 \times .1 = .38 \times .75 = .29 \text{ K}$$

$$1.25 \times 12 \times .15 \times .1 = .23 \times (.625 + 1.5) = 0.49 \text{ K}$$

$$.5 \times 11.917 \times 1.075 \times .15 \times .1 = 0.96 \times (5 + 1.5) = 6.24 \text{ K}$$

$$1.57 \text{ K}$$

$$7.02 \text{ K}$$

M<sub>a</sub> due to Vert accel. .05 G on Mass of Dam.


$$.05 \times 130.74 = 6.54 \text{ K}$$

$$M_a \text{ due to wave action} = .707 \text{ K} \cdot 1 \times (.0624 \times 12)(122) = 7.62 \text{ K}$$

$$F.S.O.T. = \frac{102.76}{(66.61 + 7.02 + 7.62 + 6.54)} = 2.08 \text{ O.K.} \quad F.S.SL = \frac{24.11 - 5.12}{(7.62 + 2.2)} = 1.93 \text{ O.K.}$$



Loc. of Res.  $\frac{182.76 - 87.79}{24.11 - 5.12 - (.05 \times 17 \times 13)} = 5.24' \div 17.17$   
0.316



$P_1 (\gamma_{dry}) = 4' \times .036 \text{ PCF} \times \frac{4' \times 1}{2} = .298^K \times 14.33 = 4.3$

$P_2 (\gamma_{wet}) = 4' \times .055 \times 13 \times 1 = 2.86^K \times \frac{13' \times 10.6'}{2} = 10.6'$

$P_3 (\gamma_{wet}) = .055 \times \frac{13^2}{2} = 4.64 \times 4.33 = 20.1^K$

Mom. @ BOT of FTG.

$P_1 = .298 \times 15.83 = 4.56^K$

$P_2 = 4 \times .055 \times 14.5 \times 1 = 3.19^K \times 7.25 = 23.13^K$

$P_3 = .055 \left( \frac{14.5^2}{2} \right) = 5.78 \times 4.03 = 23.34^K$

$\Sigma M_{\text{Top of FTG}} = 42.83^K$   $\Sigma M_{\text{Bottom of FTG}} = 55.63^K$

$A_{\text{BASE OF Stem}} = \frac{42.83}{1.44 \times 30.94} = 0.96 \text{ in}^2/\text{Ft}$

#7 @ 6"  $A_s = 1.27 > .96$   
O.K.

Mom. about Toe: Resist.

$1 \times 2 \times .15 = 0.3^K$	$\times 32.917 = 9.85^K$
$1.5 \times 33.917 \times .15 = 7.63^K$	$\times \frac{33.917}{2} = 129.42^K$
$1.5 \times 17 \times .15 = 3.83^K$	$\times 30.75 = 117.62^K$
$\frac{1.42 \times 17 \times .15}{2} = 1.81^K$	$\times 31.97 = 57.87^K$
$1 \times 120 \times 17 = 2.04^K$	$\times 33.42 = 68.17^K$
<u>15.61</u>	<u>382.96^K</u>

PROJECT Whetstone  
Gulf Camp Site Conn



FLAHERTY-GIAVARA ASSOCIATES  
 ENVIRONMENTAL DESIGN CONSULTANTS  
 ONE COLUMBUS PLAZA, NEW HAVEN, CONN 06510/203/788-1280

SHEET NO. 6 OF 7  
 BY RM DATE 7/27/91  
 CHK'D BY \_\_\_\_\_ DATE \_\_\_\_\_

$$MOT = 55.63'K \quad M_{Res.} = 382.96'K$$

$$F.S. = \frac{383}{56} = 6.84$$

$$F.S._x = \frac{15.61 \times 6}{9.26'K} = 1.01 \text{ (Low-OK)}$$

Toe butts other toe  $\therefore$  No sliding

$$x = \frac{383 - 55.6}{15.61} = 20.97' \quad e = \frac{33.917}{2} - 20.97 = 4.01$$

$$SP = \frac{15.61}{33.917} \left( 1 \pm \frac{6 \times 4.01}{33.917} \right) = \frac{1.71}{.25} = .13 \text{ feet}$$

Water level at El. 1904.8



# STABILITY ANALYSIS PROGRAM - WORK SHEET

## INPUT ENTRY

		<u>ANALYSIS CONDITION</u>				
		1	2	3	4	5
Unit Weight of Dam (K/ft <sup>3</sup> )	0	0.15	0.15	0.15	0.15	0.15
Area of Segment No. 1 (ft <sup>2</sup> )	1	14.9	14.9	14.9	14.9	14.9
Distance from Center of Gravity of Segment No. 1 to Downstream Toe (ft)	2	9.71'	9.71'	9.71'	9.71'	9.71'
Area of Segment No. 2 (ft <sup>2</sup> )	3	3	3	3	3	3
Distance from Center of Gravity of Segment No. 2 to Downstream Toe (ft)	4	3.84	3.84	3.84	3.84	3.84
Area of Segment No. 3 (ft <sup>2</sup> )	5	64.05	64.05	64.05	64.05	64.05
Distance from Center of Gravity of Segment No. 3 to Downstream Toe (ft)	6	7.97	7.97	7.97	7.97	7.97
Base Width of Dam (Total) (ft)	7	17.17	17.17	17.17	17.17	17.17
Height of Dam (ft)	8	12'	12'	12'	12'	12'
Ice Loading (K/L ft.)	9	—	5.0	—	—	—
Coefficient of Sliding	10	1.0	1.0	1.0	1.0	1.0
Unit Weight of Soil (K/ft <sup>3</sup> ) (deduct 18)	11	—	—	—	—	—
Active Soil Coefficient - Ka	12	1.0	1.0	1.0	1.0	1.0
Passive Soil Coefficient - Kp	13	—	—	—	—	—
Height of Water over Top of Dam or Spillway (ft)	14	1'	1'	5.1'	1'	6.8'
Height of Soil for Active Pressure (ft)	15	12'	12'	12'	12'	12'
Height of Soil for Passive Pressure (ft)	16	—	—	—	—	—
Height of Water in Tailrace Channel (ft)	17	—	—	—	—	—
Weight of Water (K/ft <sup>3</sup> )	18	.0624	.0624	.0624	.0624	.0624
Area of Segment No. 4 (ft <sup>2</sup> )	19	—	—	—	—	—
Distance from Center of Gravity of Segment No. 4 to Downstream Toe (ft)	20	—	—	—	—	—
Height of Ice Load or Active Water (ft) (does not include 14)	46	12	12	12	12	12
Seismic Coefficient (g)	50	—	—	—	.1	—

## RESULTS OF ANALYSIS

Factor of Safety vs. Overturning	1.04	.64	.87	1.01	0.81
Distance From Toe to Resultant	.67	-9.56	-2.47	.25	-3.77
Factor of Safety vs. Sliding	1.12	.57	.71	0.84	0.61

APPENDIX E

PREVIOUS INSPECTION REPORTS/AVAILABLE DOCUMENTS

DESIGN DATA

## FOREWORD

This campsite is located in Lewis County about 10 miles southerly along State Highway Route 12 D from Lowville, N. Y. The campsite facilities have been repeatedly damaged by high water in Whetstone Creek which flows through the campsite.

To prevent such damage in the future a dam is to be constructed on Whetstone Creek upstream from the campsite which will create an impounding basin to store a part of the flood waters.

### Hydraulics

The drainage area of Whetstone Creek above the dam site is 8.1 square miles of which it is estimated that 20 per cent is swamp or water surface, 70 per cent is wooded area and 10 per cent is pasture. The slopes on the drainage area are very moderate.

There is no gaging station on Whetstone Creek or on any other small stream in the vicinity, but for the study of the effect of regulation of spring floods the stream flow records of larger streams in the vicinity are useful. Stream flow records are available for a station on Otter Creek at Glenfield six miles from the dam site, from Sept. 30, 1924 to July 8, 1933. The drainage area of Otter Creek above the Glenfield station is 62 square miles. There are also stream flow records of Independence River at Sperryville, 12 miles distant, where the drainage area is 85 square miles, from December 7, 1927 to June 30, 1942 and at Donnattsburg, where the drainage area is 91.7 square miles from July 1, 1941 to Sept. 30, 1945. A study of all these records reveal no unusual daily discharge; the greatest being at Sperryville on April 8, 1928, which was 2990 cubic feet per second, or 35 cfs per square mile of drainage area.

The slope of the bed of Whetstone Creek through the campsite averages 2.8 feet per hundred. Assuming the value of C in Chezy formula to be 30 it is estimated that a stream bed 20 feet wide and one foot deep will accomodate 96 cfs without overflowing the banks. Assuming the entrance factor to be 0.7 in the standard formula for the flow through orifices, the data for the orifice discharge curve shown on the drawing has been computed.

### Storage Dam

After taking into account all of the stream flow data available and the computations mentioned herein it has been decided that a dam with a spillway crest at elevation 1898, U.S.C.S. datum, and 60 feet long with a 2' x 2' orifice at the stream bed level will be required to prevent the stream from overflowing its banks in the campsite and provide sufficient spillway capacity to insure the safety of the dam in the event of an extraordinary flood or the closing or partial closing of the 2' x 2' orifice.

Test pits revealed no evidence of bed rock at the dam site nor there other evidences of bed rock in the vicinity of the dam site. Under 9 to 12 inches of top soil the soil is a fairly impervious mixture of clay and gravel. To meet the soil conditions at the dam site and provide a permanent structure, a hollow reinforced concrete spillway with reinforced concrete abutments and earth embankment with reinforced concrete core wall ends to the dimensions shown on the drawings has been designed. The estimated cost of the storage dam is \$17,900.

#### Clearing

Practically all of the area subject to flooding is densely covered with brush and comparatively small trees. The area below the 1897 foot contour is 330 acres. The area above the 1897 foot contour will be flooded so seldom and for such short periods of time that clearing will not be required.

#### Roads

Parts of an abandoned railroad grade, now used as a highway, will be subject to flooding. Two methods of treating this item have been studied. The first method is to raise the grade of the low places on the present location. The second method would be to improve about 2.9 mi of abandoned town road outside the area subject to flooding. Estimate of costs of the two methods show that the second method would cost more than twice as much as the first method. The cost of raising 3750 linear feet of the railroad grade road to the cross section shown on the drawing and to a minimum grade elevation of 1898 feet is estimated to be \$6000.

#### Facilities

The existing camping and picnicking facilities in Whetstone Gulf public campsite include a modern administration building, 1/3 mile of gravel access road, one mile of water pipe line from a spring and spring house to the campsite, two sets of old latrines and a number of fireplaces and picnic tables.

The facilities to be provided by this project include a bathing pool dam, three sets of 4-unit latrines with stone-lined cesspools, one set of 12-unit bath houses, one assembly area with 1200-person capacity, 1600 linear feet of 1½ and 1-inch water pipe and 14 combination water outlets.

#### Bathing Pool Dam

The bathing pool dam will consist of a low reinforced concrete spillway 60 feet long with stone masonry abutments all founded on bed rock with a low earth embankment at each end to an elevation 6 feet above the top of the concrete spillway. The spillway will be equipped with flashboards 3 feet high supported to 2" diameter standard iron pipes 5 feet apart designed to fail when overtopped by two feet of water. The estimated cost of the bathing pool dam is \$5100.


STRUCTURAL CALCULATIONS

Subject Whitstone Gull - N.Y.S. Conserv. Dept

Sheet No. 1

Total No. Sheets 1

Date                     



Computed by Peck Date 2/4/60  
Checked by                      Date

Subject Whetstone Gully - N.Y.S. Conserv. Dept

Sheet No. 2

Total No. Sheets       

Date       

# OVERTURNING MOMENTS (ctr. of Moments at heel)

(1) = $0.5 \times 12.0' \times \frac{1}{2} \times 1.0' \times 150 \frac{\text{#}}{\text{ft}^3} = 450 \text{ #}$	$\times 13.33'$	=	6,000 <sup>1#</sup>
(2) = $1.5' \times 12.0' \times 1.0' \times 150 \frac{\text{#}}{\text{ft}^3} = 2700 \text{ #}$	$\times 12.42'$	=	33,600 <sup>1#</sup>
(3) = $10.5' \times 11.67' \times \frac{1}{2} \times 1.0' \times 150 \frac{\text{#}}{\text{ft}^3} = 9200 \text{ #}$	$\times 7.78'$	=	71,600 <sup>1#</sup>
(4) = $1.5' \times 11.67' \times 1.0' \times 150 \frac{\text{#}}{\text{ft}^3} = 2635 \text{ #}$	$\times 5.83'$	=	15,300 <sup>1#</sup>
$P_{H1} = 95 \text{ #}$	$\times 12.50'$	=	1,190 <sup>1#</sup>
$P_{H2} = 985 \text{ #}$	$\times 5.83'$	=	5,710 <sup>1#</sup>
$P_{H3} = 5,150 \text{ #}$	$\times 3.92'$	=	20,200 <sup>1#</sup>
$21,215 \text{ #}$			153,600 <sup>1#</sup>
$P_{H1} = 1090 \times 6.75'$		=	6,350 <sup>1#</sup>
$P_{H2} = 5730 \times 5.67'$		=	32,540 <sup>1#</sup>
$P_{H3} = 1150 \times 0.75'$		=	860 <sup>1#</sup>
			193,350 <sup>1#</sup>

$$193,350 \text{ #} + 21,215 \text{ #} = 9.12'$$

$$\frac{1}{3} \times 13.67' = 9.23'$$

Section O.K. within  $\frac{1}{3}$  part of base.

Factor of Safety vs. Sliding:

$$\Sigma \text{ Horizontal thrusts} = 1,090 \text{ #} + 5,730 \text{ #} + 1,150 \text{ #} = 7,970 \text{ #}$$

$$\Sigma \text{ Vertical load} = 21,215 \text{ #}$$

$$\text{Factor of Safety} = \frac{21,215 \text{ #}}{7,970 \text{ #}} = 2.68 \text{ to } 1$$

Computed by        Date       

Checked by        Date



Subject Whetstone Gulf - N.Y.S. Conserv. Dept.


Sheet No. 3

Total No. Sheets       

Date       

# INVESTIGATION OF ABUTMENT WALL SECTION.

CASE I: Water Surface as Shown.



Earth behind wall:  
assumed as Clay, gravel  
and sand, dry @ 100 #/ft.<sup>3</sup>  
Equiv. Fluid Pr. = 25 #/ft.<sup>2</sup>  
" Fl. Pr. Submerged = 51.9 #/ft.<sup>2</sup>  
Clay, gravel and sand  
Submerged wt @ 65 #/ft.<sup>3</sup>  
Equiv. Fl. Pr. = 39.7 #/ft.<sup>2</sup>  
Wt of Water = 62.5 #/ft.<sup>3</sup>  
Wt of Submerged Conc. 90 #/ft.<sup>3</sup>  
Assume 1'-0" width of wall.

Values of P at top of Footing:

$$P_1 = 4.0' \times 25 \text{ #/ft}^2 \times \frac{1}{2} \times 4.0' \times 1.0' = 200 \text{ #} \times 14.33' = 2870 \text{ #}$$

$$P_2 = 4.0' \times 51.9 \text{ #/ft}^2 \times 13.0' \times 1.0' = 2700 \text{ #} \times 6.50' = 17,550 \text{ #}$$

$$P_3 = 13.0' \times 39.7 \text{ #/ft}^2 \times \frac{1}{2} \times 13.0' \times 1.0' = 2930 \text{ #} \times 4.33' = 12,690 \text{ #}$$

Values of P at bottom of Footing:

$$P_1 = 4.0' \times 25 \text{ #/ft}^2 \times \frac{1}{2} \times 4.0' \times 1.0' = 200 \text{ #} \times 15.83' = 3,170 \text{ #}$$

$$P_2 = 4.0' \times 51.9 \text{ #/ft}^2 \times 14.5' \times 1.0' = 3010 \text{ #} \times 7.25' = 21,800 \text{ #}$$

$$P_3 = 14.5' \times 39.7 \text{ #/ft}^2 \times \frac{1}{2} \times 14.5' \times 1.0' = 3,750 \text{ #} \times 4.83' = 18,130 \text{ #}$$

Computed by Peck Date 3/4/60

Checked by        Date

INVESTIGATION OF ABUTMENT WALL SECTION (Continuation)CHSE I

① = $4.0' \times 1.5' \times 1.0' \times 150 \#/ft^3$	= 900 #	x 3.17'	= 2,850 #
② = $4.0' \times 0.33' \times \frac{1}{2} \times 1.0' \times 150 \#/ft^3$	= 990 #	x 2.30'	= 2,280 #
③ = $4.0' \times 0.33' \times \frac{1}{2} \times 1.0' \times 100 \#/ft^3$	= 65 #	x 2.17'	= 140 #
④ = $4.0' \times 1.08' \times 1.0' \times 100 \#/ft^3$	= 435 #	x 1.59'	= 670 #
⑤ = $4.0' \times 1.0' \times 1.0' \times 100 \#/ft^3$	= 400 #	x 0.68'	= 200 #
⑥ = $13.0' \times 1.5' \times 1.0' \times 90 \#/ft^3$	= 1755 #	x 3.17'	= 5,560 #
⑦ = $13.0' \times 0.33' \times 1.0' \times 90 \#/ft^3$	= 390 #	x 2.25'	= 880 #
⑧ = $13.0' \times 1.08' \times \frac{1}{2} \times 1.0' \times 90 \#/ft^3$	= 635 #	x 1.72'	= 1,090 #
⑨ = $13.0' \times 1.08' \times \frac{1}{2} \times 1.0' \times 65 \#/ft^3$	= 455 #	x 1.36'	= 620 #
⑩ = $13.0' \times 1.0' \times 1.0' \times 65 \#/ft^3$	= 845 #	x 0.50'	= 420 #
	<u>6,870 #</u>		<u>14,710 #</u>
(11) = $10.92' \times 1.5' \times 1.0' \times 90 \#/ft^3$	= 1475 #	x 5.96'	= 8,065 #
(12) = $1.0' \times 2.0' \times 1.0' \times 90 \#/ft^3$	= 185 #	x 1.0'	= 185 #
	<u>8,530 #</u>		<u>22,960 #</u>

Values at top of footing:

$$\Sigma (1) \text{ to } (10) inc = 6,870 \# = 14,710 \#$$

$$\Sigma P = 33,100 \#$$

$$47,810 \#$$

Values at bottom of footing:

$$\Sigma (1) \text{ to } (12) inc = 8,530 \# = 22,960 \#$$

$$\Sigma P = 47,810 \#$$

$$66,060 \#$$

$$66,060 \# \div 8,530 \# = 7.76'$$

$$\frac{2}{3} \text{ point of base} = 10.92 \times \frac{2}{3} = 7.28' \text{ O.K.}$$

INVESTIGATION OF WALL STEMOverturning moment at top of footing =  $33,100 \#'$ 

$$\text{Wall Section: } 1.5' \times 17.0' \times 1.0' \times 150 \#/ft^3 = 3820 \#$$

$$1.92 \times 17.0' \times 1.0' \times \frac{1}{2} \times 150 \#/ft^3 = 1810 \#$$


$$5630 \#$$

$$\text{Req'd } A_s = \frac{33,100 \# \times 12}{18,000 \times 0.875 - 31.56} = \frac{5630 \#}{18,000}$$

$$= 0.798 \text{ in}^2 - 0.313 \text{ in}^2 = 0.790 \text{ in}^2$$

$$\text{Used } 8 \# \text{ bars @ } 6 \text{ in} = 1.202 \text{ in}^2 \text{ O.K.}$$

Spacing of bars could be increased.

Computed by ReckDate 3/7/60Checked by ReckDate 3/7/60

Subject Whetstone Gulf - N.Y. State Conserv. Dept.

Total No. Sheets       

Date       

INVESTIGATION OF ABUTMENT WALL SECTION.

CASE II: Assuming no percolation of water to submerge earth behind wall.  
Buoyancy for Concrete wall Section only.

Value of P at top of Footing:

$$P_1 = 17.0' \times 25.0' \text{ ft}^2 \times \frac{1}{2} \times 17.0' \times 1.0 = 3.610' \times 5.67 = 20,450' \text{ ft}$$

Value of P at bottom of Footing:

$$P_1 = 19.0' \times 25.0' \text{ ft}^2 \times \frac{1}{2} \times 19.0' \times 1.0 = 4.510' \times 6.33 = 28,600' \text{ ft}$$

① 4.0' x 1.5' x 1.0' x 150 # ft <sup>3</sup>	= 900 #	x 3.17'	= 2,850' <sup>12</sup>
② 4.0' x 0.33' x 1.0' x 1/2 x 1.0' x 150 # ft <sup>3</sup>	= 990 #	x 2.30'	= 2,280' <sup>12</sup>
③ 4.0' x 0.33' x 1.0' x 1/2 x 1.0' x 100 # ft <sup>3</sup>	= 65 #	x 2.19'	= 140' <sup>12</sup>
④ 4.0' x 1.08' x 1.0' x 100 # ft <sup>3</sup>	= 435 #	x 1.54'	= 670' <sup>12</sup>
⑤ 4.0' x 1.0' x 1.0' x 100 # ft <sup>3</sup>	= 400 #	x 0.50'	= 200' <sup>12</sup>
⑥ 13.0' x 1.5' x 1.0' x 90 # ft <sup>3</sup>	= 1755 #	x 3.17'	= 5,560' <sup>12</sup>
⑦ 13.0' x 0.33' x 1.0' x 90 # ft <sup>3</sup>	= 390 #	x 2.25'	= 880' <sup>12</sup>
⑧ 13.0' x 1.08' x 1/2 x 1.0' x 90 # ft <sup>3</sup>	= 635 #	x 1.72'	= 1,090' <sup>12</sup>
⑨ 13.0' x 1.08' x 1/2 x 1.0' x 100 # ft <sup>3</sup>	= 700 #	x 1.38'	= 950' <sup>12</sup>
⑩ 13.0' x 1.0' x 1.0' x 100 # ft <sup>3</sup>	= 1300 #	x 0.50'	= 650' <sup>12</sup>
	<u>7570 #</u>		<u>15,270' <sup>12</sup></u>
⑪ 10.92' x 1.5' x 1.0' x 90 # ft <sup>3</sup>	= 1475 #	x 5.46'	= 8,065' <sup>12</sup>
⑫ 1.0' x 2.0' x 1.0' x 90 # ft <sup>3</sup>	= 185 #	x 1.0'	= 185' <sup>12</sup>
	<u>9,230</u>		<u>23,520' <sup>12</sup></u>

Values at top of footing:

Σ (1) to (10) inc.

Σ P

$$= 7570' \text{ ft}$$

$$= 15,270' \text{ ft}$$

$$= 23,450' \text{ ft}$$

$$= 35,710' \text{ ft}$$

Values at bottom of footing:

Σ (1) to (12) inc.

Σ P

$$= 9,230' \text{ ft}$$

$$= 23,520' \text{ ft}$$


$$= 28,600' \text{ ft}$$

$$= 52,320' \text{ ft}$$

$$52,320' \text{ ft} \div 9,230' = 5.67'$$

$$\frac{2}{3} \text{ point of base} = 10.92' \times \frac{2}{3} = 7.28' \text{ o.w.}$$

INVESTIGATION OF FLASH BOARDS



$$187.5' \times 6.25' \times 3.0' = 187.5' \times 1.5 = 386.25' \text{ ft}$$

$$(250.0' - 62.5') \times 3.0' \times \frac{1}{2} = 386.25' \times 1.0 = 386.25' \text{ ft}$$

$$573.75' \times 1.35 = 773.56' \text{ ft}$$

5.0' ctr. to ctr. supports

$$\text{Cantilever Mom} = 573.75' \text{ ft} \times 5.0' \times 1.35 = 3,875' \text{ ft}$$

$$\text{Reg'd } \frac{1}{4} = \frac{3,875' \text{ ft} \times 1.2}{72,000' \text{ ft}^2} = 0.65 \text{ in}^3$$

Computed by Peck

Date 3/7/60

$$1 \frac{1}{2}" \text{ Std pipe} = 0.310 \text{ in}^3$$

Checked by       

Date

TECHNICAL SPECIFICATIONS

## SPECIAL SPECIFICATIONS

### 1. Borrow Pits

All materials required for backfill and for earth embankment, which are not available from required excavation, shall be taken from borrow pits. The borrow pit or pits may be on State owned land, if suitable material is found on State owned land. The borrow pit sites shall, however, be approved by the Conservation Department representative before any borrow is taken from them. If sufficient suitable material is not found on State owned land, the contractor will be required to obtain borrow from privately owned land at his own expense. The sites of all borrow pits shall be stripped of top soil and other materials not suitable for earth embankment. All borrow pits on State owned land shall be left so they will be self-draining. Payment for the work described in this paragraph will be included in the price bid for embankment.

### 2. Preparation of Earth Foundation for Concrete Slab

When the excavation for the reinforced concrete floor slab has reached the stage within 6 inches of the finished subgrade or before, the area being worked on shall be unwatered and kept unwatered until the reinforced concrete slab has been placed. The final excavation to subgrade shall be done by hand. If the excavation is extended below the specified subgrade without written direction, this overcut shall not be backfilled with earth but with concrete at the contractor's expense. The excavation for the downstream face of the cutoff wall under the heel of the deck and the upstream face of the cutoff wall under the downstream end of the apron shall be made to neat lines so that no forms will be required. Payment for the work described in this paragraph shall be included in the unit price bid for excavation (Item 4) and diversion and care of water during construction (Item 3).

### 3. Preparation of Rock Foundation for Stone Masonry and Concrete

The surface of all rock foundations upon which or against which stone masonry or concrete is to be placed shall be prepared to provide adequate bond between the rock and the stone masonry or concrete by roughening and cleaning the rock surface. All rock fragments that may be pried loose with a crowbar, spalls, dirt, gravel and other objectionable materials shall be removed from the surface of the rock. Immediately before placing stone masonry or concrete upon or against any rock surface, the surface shall be thoroughly cleaned by the use of stiff brooms, hammers, picks, jets of water, and air applied at high velocity. After cleaning and before any stone masonry or concrete is placed, all water shall be removed from depressions so as to permit thorough inspection and proper bond of stone masonry and concrete with the foundation rock. Payment for the work described in this paragraph shall be included in the price bid for excavation.

## ITEM SPECIFICATIONS

### Item 1 - Clearing and Grubbing

Under this item the areas to be used for the storage dam, the bathing pool, the area to be flooded by the bathing pool dam when there is six inches of water over the top of the flashboards and all other necessary structures and improvements where this work is not specifically included in that item shall be cleared of all trees, stumps, roots, brush and rubbish. No other clearing shall be permitted without the specific approval of the Conservation Department representative. All timber and wood shall remain the property of the State of New York and shall be piled as and where directed by the representative of the Conservation Department.

All stumps, roots, brush, rubbish, and unusable timber shall be hauled to open areas and completely burned or otherwise disposed of as directed. Extreme care shall be taken so that no trees may be scorched or damaged. Payment will be made for the lump sum bid for this item. This item does not include any work to be done on the area to be flooded by the storage dam which work will be paid for under Item 2.

### Item 2 - Clearing Flow

Under this item all of the area subject to flow by the storage dam below the 1897 contour, U.S.G.S. datum, shall be cleared of all standing and down vegetable growth and other articles that might float. All brush and trees four inches in diameter, 12 inches above the ground at their bases, or less, shall be cut within 4 inches of the ground. All trees over four inches in diameter, 12 inches above the ground at their bases, shall be cut within a distance from the ground equal to the diameter of the tree 12 inches above the ground. All timber and wood shall remain the property of the State of New York and shall be piled as and where directed by the representative of the Conservation Department. All unusable wood, timber, brush and rubbish shall be completely burned or otherwise disposed of as directed. No stick or other object more than 20 inches in length that may float shall be left on the area to be cleared. Payment will be made for the number of acres cleared at the unit price bid.

### Item 3 - Diversion and Care of Water During Construction

The contractor shall construct and maintain all necessary cofferdams, channels, flumes, or other temporary diversion and protective works shall furnish all materials required therefor; and shall furnish, install, maintain, and operate all necessary pumping and other equipment for unwatering the various parts of the work, and for maintaining the foundation, cutoff trenches and other parts of the work free from water as required for constructing each part of the work. The contractor shall determine for himself the probable maximum discharges that he will have to provide for with cofferdams and other diversion facilities.

After having served their purpose all cofferdams and other temporary protective works for both the storage dam and the bathing pool dam shall be removed or leveled to give a slightly appearance as directed. Payment will be made for the lump sum bid for this item.

**Item 4 - Excavation, except Stripping**

This item includes the removal of all earth or rock to the lines and grades shown on the plans for the storage dam, the bathing pool dam, the assembly area piers and at such other places as directed by the representative of the Conservation Department. Maximum payment lines shall not exceed two feet outside the base of the masonry with slopes of 2 on 1. The excavation for the reinforced concrete foundation slab and apron of the storage dam shall not exceed the depth shown on the drawing except in the event the material at the bottom of the trench for the cutoff wall under the heel of the deck is, in the opinion of the Conservation Department representative, not sufficiently impervious, in which event the contractor, upon written order, shall continue the trench in whole or in part to a depth not exceeding three feet below the grade shown on the drawing. All excavated material suitable for backfill may be used for that purpose and all other excavated material shall be disposed of where it will not be unsightly or as directed by the Conservation Department representative. Payment will be made for the actual number of cubic yards of earth and rock excavated within the maximum payment lines exclusive of stripping which will be paid for under Item 5.

**Item 5 - Stripping**

Under this item the sod and other vegetable matter shall be removed from the areas to be used for the earth embankment portions of the storage dam and the bathing pool dam down to mineral soil--an average depth of 9 inches of stripping. All stripping suitable for growing vegetation shall be stored for spreading on the top and downstream slopes of the earth embankment sections of the two dams. The cost of removing and piling the stripping will be paid for under this item at the unit price bid. The cost of spreading the stripping on the top and downstream slopes of the earth embankment sections of the two dams will be paid for as earth embankment under item 7.

**Item 6 - Earth Embankment for Road**

This item covers the furnishing and depositing of mineral soil for widening and raising the grade of the old railroad grade road as shown by the plan, profile and typical cross section on the drawing. The material furnished shall be free from roots and other vegetable matter. All stones over 5 inches in greatest dimension shall be removed from the middle 10-foot area to the outside of the fill. Payment will be made for the actual number of cubic yards of acceptable fill material in place, exclusive of the riprap, at the unit price bid for this item.

Item 7 - Earth Embankment for Dams

This item includes the earth embankment parts of the dams and the backfill back of the retaining walls and both sides of the core walls. For backfilling only clear mineral soil free from roots and other vegetable matter shall be used. The backfill shall be deposited in layers not more than 6 inches in thickness and thoroughly tamped in place before the next layer is deposited. The fill material shall have a moisture content such that when squeezed in the hand it will form a roll that will stay together when held horizontal by one end. Before depositing any earth embankment the foundation shall be free from roots or other vegetable matter. Earth embankment shall be placed in layers not more than 6 inches in thickness and each layer shall be thoroughly compacted by rolling, tamping, or by other satisfactory means. The earth for embankment shall be free from roots and other vegetable matter. No stones having maximum dimensions of more than 5 inches shall be left in the earth embankment. No material shall be placed in embankment when either the material or the foundation or embankment on which it would be placed is frozen. The embankment shall conform to the lines shown on the drawings. Payment will be made for the number of cubic yards actually placed in backfill and earth embankment, exclusive of the riprap yardage, but inclusive of the stripping yardage which shall be spread evenly on the top and downstream slopes of the earth embankment sections of the two dams and on the upstream slopes of the two dams from the top of the riprap to the top of the dam s, and within the lines shown on the drawings at the unit price bid for earth embankment.

Item 8 - Concrete for Dams

For both the storage dam and the bathing pool dam, the concrete shall be proportioned as follows: one part of portland cement, to two parts of sand and  $3 \frac{3}{4}$  parts of broken stone or screened, washed, and well-graded gravel. The proportions of sand and coarse aggregate may be slightly varied to obtain a denser concrete if so directed by the representative of the Conservation Department on the job. Only sufficient water shall be used to make a workable consistency. The slump, as shown on the standard American Society of Testing Materials test, shall not exceed 4 inches. At least one slump test shall be made for each pour of concrete.

The cement used shall have been tested and approved by the State Department of Public Works. The sand to be used shall be approved by the Conservation Department and washed. A sample of the sand it is proposed to use shall be forwarded to the Conservation Department, Albany, N. Y., prepaid, in sufficient time to have tests made and a report sent back to the contractor in time not to delay the progress of the work. Good, clean, hard, broken stone or gravel will be acceptable for coarse aggregate. The maximum size of aggregate permitted will pass through a 24 screen.

The mixing of the concrete, unless otherwise specifically authorized, shall be done in a batch mixer of approved type which will insure a uniform distribution of the materials throughout the mass. The entire contents of the drum shall be discharged before recharging. The volume of the mixed material per batch shall not exceed the



manufacturer's rated capacity of the mixer. The mixing of each batch shall continue not less than two minutes after all materials are in the mixer, during which time the mixer shall rotate at a peripheral speed of about 200 feet per minute.

Good, substantial, well-braced forms shall be used. The concrete shall be placed in the forms and well spaded or vibrated before it has taken its initial set. Before placing freshly mixed concrete against concrete that has taken its initial set, all laitance shall be removed, the surface thoroughly wetted and cleaned, and a layer of mortar  $\frac{3}{4}$  inch thick spread over the surface. All concrete shall be kept moist for a period of two weeks, protected from the sun's rays for three days, and the temperature kept above 50°F for three days.

Expansion joints and construction joints shall be located where, and only where, shown on the drawings or directed by the Conservation Department representative and shall conform with the detail shown on the drawing or as directed in writing by the Conservation Department representative. The contractor shall furnish all labor, materials, tools, and equipment required for this item except the reinforcing steel and sheet copper and asphalt joint filler for expansion joints which will be paid for under items 10, 11, and 12. Payment will be made for the number of cubic yards of concrete for dams in place, except no payment will be made for an over run in concrete due to an overcut in excavation without a written order, at the unit price bid for concrete for dams.

#### Item 9 - Concrete other than for Dams

This item covers the materials and labor required to construct the concrete piers supporting the log seats and the speaker's platform at the assembly area, and filling cracks and small depressions in the bathing pool bottom as directed. The concrete shall be proportioned as follows: 1 part of portland cement to 2½ parts of sand and 4½ parts of broken stone or gravel measured by volume. The proportions of sand and coarse aggregate may be slightly varied to obtain a denser concrete if so directed by the representative of the Conservation Department on the job. Only sufficient water shall be used to make a workable consistency. The slump, as shown on the standard American Society of Testing Materials test, shall not exceed 4 inches. At least one slump test shall be made for each pour of concrete.

The cement used shall have been tested and approved by the State Department of Public Works. The sand to be used shall be approved by the Conservation Department and washed. A sample of the sand it is proposed to use shall be forwarded to the Conservation Department, Albany, N. Y., prepaid, in sufficient time to have tests made and a report sent back to the contractor in time not to delay the progress of the work. Good, clean, hard broken stone or gravel will be acceptable for coarse aggregate. The maximum size of aggregate permitted will pass through a 2½ screen.

The mixing of the concrete, unless otherwise specifically authorized, shall be done in a batch mixer of approved type which will insure a uniform distribution of the materials throughout the mass. The entire contents of the drum shall be discharged before recharging. The volume

of the mixed material per batch shall not exceed the manufacturer's rated capacity of the mixer. The mixing of each batch shall continue not less than two minutes after all materials are in the mixer, during which time the mixer shall rotate at a peripheral speed of about 200 feet per minute.

**Item 10 - Reinforcing Steel**

Under this item round deformed bars of the size and location shown on the drawings shall be incorporated in the structures as shown. All bars shall meet the physical properties and tests of A.S.T.M. specifications A-15-39 for intermediate or hard grade. The bars when used shall be free from dirt and rust. The bars shall be accurately positioned and secured against displacement. The bars shall be fastened together at crossings with suitable clips or wired together with not smaller than No. 18 gauge annealed wire at sufficient intervals to prevent displacement. The bars shall be supported by metal or concrete chairs, spacers, or by metal hangers. When splicing bars they shall be lapped not less than 40 bar diameters. No bars shall be more than 5 per cent under the standard weight for bars of the size specified. No direct payment will be made for the tie wire, clips, chairs, hangers, etc. as the cost of these items will be included in the unit price bid for reinforcing steel. Payment will be made for the actual number of pounds of steel reinforcing in place.

**Item 11 - Sheet Copper**

No. 20 gauge annealed sheet copper shall be cut into strips 12 inches wide folded as shown on the drawing and placed in all expansion joints to make watertight barriers at the expansion joints. Payment will be made for the number of pounds of sheet copper in place.

**Item 12 - Asphalt Joint Filler**

To make room for expansion and to protect the sheet copper water stop, 1/2 inch of asphalt joint filler shall be spread on the first placed face of the expansion joint, after which the concrete on the other side of the expansion joint shall be placed. Care shall be taken that the layer of joint filler is not disturbed nor the concrete next to it is not porous. The asphalt joint filler shall consist of not less than 17 per cent of pure asbestos fiber and not more than 50 to 60 per cent of asphalt, 5 to 6 per cent of pitch and 30 to 40 per cent of volatile spirits.

**Item 13 - No. 2 Crushed Stone Underdrains**

This item covers the furnishing of all materials and labor for the filling of drainage ditches under the storage dam and apron with No. 2 crushed stone at the locations shown on the drawings. The crushed stone shall be clean, hard and durable and shall be slightly compacted by tamping. After compaction, the stone filled trenches shall be covered with one-ply tarpaper. The excavation of trenches will be included in Item 4-Excavation. All other costs including the tarpaper will be included in the unit price bid for No. 2 crushed stone underdrains in place.

Item 14 - Stone Riprap

Under this item the contractor shall furnish and place field or quarry stone riprap on the upstream slope of the earth embankment sections of the two dams to the lines and grades shown on the drawings and on the easterly slope of the road embankment along the old railroad grade location. The stones furnished shall be hard and durable one-man or two-man stones. The toe of the riprap shall be set in a trench at least 12 inches deep with one side of the trench parallel with the face of the riprap and 12 inches below it, and the other side of the trench normal to the face of the riprap as shown on the drawings. The riprap shall be 12 inches thick, including 3-inch sand cushion. The stones shall be hard placed with principal bedding planes generally normal to the face of the riprap and with the interstices between the larger stones filled with spalls or smaller stones so as to make an even and close finished surface. No direct payment will be made for the necessary excavation to prepare the bed for the riprap, but the cost of such excavation will be included in the unit price bid for stone riprap. Payment will be made for the number of cubic yards in place, including the sand cushion, at the unit price bid for this item.

Item 15 - 4-inch Vitrified Pipe, 2-foot lengths

Under this item the contractor shall furnish and incorporate in the storage dam at the locations shown on the drawing common 4-inch vitrified sewer pipe to conduct water from the underdrainage system through the cutoff walls. Payment will be made for the number of linear feet of pipe incorporated in the work as shown on the drawing or as directed by the Conservation Department representative at the unit price bid.

Item 16 - Gravel Surfacing for Road

This item covers the furnishing and spreading of a 6-inch layer, loose measure, of run-of-bank gravel on the raised railroad grade road as shown on the drawing. All stones over 2½ inches in greatest dimension shall be screened or cast out. If ruts or other depressions develop during the placing of the gravel surfacing they shall be brought to grade by the addition of more gravel. The gravel shall be of a quality approved by the Conservation Department representative. Payment will be made for the number of cubic yards of gravel spread on the road, exclusive of the stones screened or cast out, at the unit price bid.

Item 17 - Gravel Surfacing for Assembly Area

This item covers the furnishing and spreading of a 2-inch layer, loose measure, of run-of-bank gravel over the entire assembly area except the area occupied by the speaker's platform and the piers supporting the log seats. All stones over 1½ inches in greatest dimension shall be screened or cast out. The gravel shall be of a quality approved by the Conservation Department representative. Payment will be made for the number of cubic yards of gravel spread on the assembly area, exclusive of the stones screened or cast out, at the unit price bid.

Item 18 - Stone Masonry

The abutments of the bathing pool shall consist of uncoursed rubble masonry laid with cement and sand mortar joint. Skilled stone masons shall be employed for the placing of the stone masonry. The stones shall be prepared for laying by removing the sharp projections and weak angles and all dust and dirt and wetting the stone. The stones shall generally be laid on their broadest faces and headers and stretchers shall be alternated so as to effectively bond the work together. Headers shall comprise at least 25% of the mass and 25% of the area of the faces. The vertical joint between any two stones shall not be directly above the vertical joint between two stones immediately below. To level the bed to receive a stone, spalls or stone chips shall be placed in a mortar bed and a generous layer of mortar spread over the area to be covered by the stone. Extreme care shall be exercised to make sure that all joints, both horizontal and vertical, shall be completely filled with mortar. The mortar used shall consist of one part of portland cement and two parts of sand. The cement used shall be approved by the Conservation Department, and sand to be used shall be from a pit or pits approved by the Conservation Department and washed. The contractor shall furnish all materials, tools, and equipment required for the work described in this paragraph for the unit price bid for stone masonry.

Item 19 - 2½-inch Galvanized iron pipe sleeves

This item covers the furnishing and installing of 2½-inch diameter standard galvanized iron pipe sleeves in the crest of the bathing pool dam as shown on the drawing. The sleeves shall be accurately set as to spacing, alignment and verticality and shall be securely fastened in place so as not to be displaced while the concrete is being placed around them. The bottoms of the sleeves shall be closed by caps or other means to prevent the fresh concrete from entering the sleeves. The top of the sleeves shall be flush with the top of the concrete spillway. Payment will be made for the number of linear feet of 2½-inch standard galvanized iron pipe properly incorporated in the work.

Item 20 - 2-inch Galvanized Iron Pipe Flashboard Supports

This item covers the furnishing and installing of 2-inch standard galvanized iron pipe flashboard supports in sleeves set in the crest of the bathing pool dam as shown on the drawing. Payment will be made for the number of linear feet of 2-inch standard galvanized iron pipe properly incorporated in the work.

Item 21 - 3-inch Oak Stop Planks

This item covers the furnishing and installing of 3-inch T&G oak stop planks in the bathing pool dam as shown on the drawing. The stop planks shall be made watertight by tacking sheet rubber or canvas to the upstream side of the stop planks so as to prevent water from passing under or around the ends of the stop planks or by other approved method. Payment will be made for the lump sum bid for this item.

Item 22 - 2-inch Flashboards

This item covers the furnishing and installing of 2-inch T&G spruce hemlock or yellow pine flashboards on the bathing pool dam as shown on the drawing. The flashboards shall be made watertight by tacking sheet rubber or canvas to the upstream side of the flashboards so as to prevent water from passing under, around the end, or between the flashboards or by other approved method. Payment will be made for the lump sum bid for this item.

Item 23 - Water lines

This item covers the extension of the existing water supply system to connect it to the new outlets and the pipe line to the administration building. This will require the furnishing and laying of 1250 linear feet of 1½-inch and 350 linear feet of 1-inch galvanized iron pipe with all the necessary fittings, such as tees, unions, elbows, reducers, drains and shutoffs at the locations shown on the drawing or as directed by the Conservation Department representative. The pipe shall be laid about one foot below the ground surface and all dips shall be provided with drains and shutoffs. The cost of excavating trenches for the pipe and backfilling them shall be included in this item. Payment will be made for the completed extension of the water supply system as shown on the drawing or outlined herein for the lump sum bid for this item.

Item 24 - Water Outlets

This item covers the furnishing of all materials and labor for the installation of combination self-closing drinking fountains and self-closing hydrants at the locations shown on the drawings or directed by the Conservation Department representative. The materials required for each outlet include the following:

- 1 cu. yd. of No. 3 broken stone
- 4 lin. ft. of 6" vit. tile pipe
- 20 lin. ft. of 4" vit. tile pipe
- 2 7½-inch diameter brass strainers
- 2 14" stepping logs for children, bolted to 14" post 4 feet long with a ½" bolt 42 inches long and to the ground by a ½" bolt 30 inches long
- 1 self-closing fountain
- 1 ½" self-closing faucet

The unit price bid for this item shall include the necessary excavation and backfill, all plumbing and all cleanup as directed by the Conservation Department representative.

Item 25 - Removing Pine Trees

This item covers the painstaking removal of trees from a white pine plantation at the site of the assembly area and the delivery of the trees to the Conservation Department representative at the campsite for replanting. Only the trees designated by the Conservation

Department representative for removal shall be removed. Trees bordering on the assembly area and not designated to be removed shall be protected from damage. The time and method of removal of the trees shall be approved by the Conservation Department representative. Payment will be made for the number of trees removed and delivered to the Conservation Department at the unit price bid.

**Item 26 - Smoothing Assembly Area Ground**

This item covers the backfilling of the depressions left by the removal of the pine trees and the filling of other depressions so as to make a fairly even surface over the assembly area. Payment will be for the number of square yards smoothed at the unit price bid.

**Item 27 - Dowels**

Under this item round deformed steel bars of the diameter and length shown on the drawing shall be furnished and set in the concrete piers to hold in place the 8-inch diameter floor joists for the speaker's platform and the 14-inch diameter log seats for the assembly area. The dowels shall be set in the centers of the tops of the piers and vertical. Payment will be made for the number of pounds of dowels in place at the unit price bid.

**Item 28 - 8-inch Logs for Platform Floor Joists**

This item covers the furnishing and incorporating in the assembly area speaker's platform 8-inch diameter floor joists. The logs shall be peeled hemlock sound and straight. They shall be dapped on the under side to fit the concrete piers and fastened to the piers by one 3/4-inch dowel at each pier. The upper side of the logs shall be hewed or sawed to a level surface so that when the plank floor is in place it will be level and each plank shall be supported by each of the four floor joists. At each end of the platform 8-inch diameter logs shall be fitted in between the floor joists as shown on the drawing. Payment will be made for the number of board feet, computed by the Doyle rule, of 8" diameter logs incorporated in the work at the unit price bid.

**Item 29 - 14-inch Log Seats**

This item covers the furnishing, fitting, and placing of 14-inch diameter log seats in the assembly area in compliance with the details shown on the drawing. The logs shall be peeled hemlock, sound, straight, and free of sharp knots. They shall be dapped on the under side to fit the concrete piers and shall be fastened to the piers by one 3/4-inch dowel at each end of each log. 3/4-inch holes shall be bored in the bottoms of the logs to engage 3/4-inch dowels set in the top of the concrete piers. The upper side of the logs shall be hewed or sawed to a smooth surface and to the slope and width shown on the drawing. Payment will be made for the number of board feet, computed by the Doyle rule, of 14-inch logs made into log seats at the unit price bid.



**Item 30 - 2-inch Plank Floor for Speaker's Platform**

This item covers the furnishing of 2-inch hemlock, spruce, or yellow pine plank d 4s and 40 d common nails and the labor of securely nailing the plank to the 8-inch diameter floor joists. The plank shall be 12 feet long and of random widths and shall be laid one half inch apart. Payment will be made for the number of board feet of plank in place at the unit price bid.

**Item 31 - Cesspools, Stone-lined**

One stone-lined cesspool shall be constructed for each set of two 4-unit latrines at the location shown on the drawing or as directed by the Conservation Department representative. The walls shall be of dry stone masonry with open joints. Care shall be observed to break vertical joints, but vertical joints may be two inches wide. The concrete and reinforcing in the top shall conform to the specifications for those items. No direct payment will be made for excavation or backfill. Payment will be made for the number of cesspools constructed at the unit price bid. With the written approval of the Conservation Department representative, log-lined cesspools may be substituted for stone-lined cesspools at the unit price bid for stone-lined cesspools.

**Item 32 - 24-inch Corrugated Galvanized Iron Pipe, 14-gage**

This item includes the furnishing and laying of 24-inch diameter, 14-gage galvanized corrugated iron pipe culverts with the necessary connecting bands at the locations shown on the drawings or as directed by the Conservation Department representative on the work. It also includes the necessary excavation and backfill required to properly lay the culverts, but does not include the excavation of drainage ditches leading from the culverts. The culverts shall be so placed that there will be at least one foot of cover over them when the road is completed. The culverts shall be supported on original ground throughout their entire length and the backfill shall be hand tamped so as to completely fill the trench under and both sides of the culvert. Payment will be made for the number of linear feet of pipe in place at the unit price bid.

SCHEDULE AND ESTIMATE OF COST

Item				
1	Clearing and Grubbing	All	L.S.	\$200.00
2	Clearing Flow	330 acres	at \$50.00	16500.00
3	Diversion and Care of Water during construction	All	L.S.	700.00
4	Excavation, except stripping	670 cu.yd. at	2.00	1340.00
5	Stripping	304 cu. yd. at	0.50	152.00
6	Earth Embankment for Road	5000 cu. yd. at	0.60	3000.00
7	Earth Embankment for Dams	2180 cu. yd. at	1.50	3270.00
8	Concrete for Dams	613 cu. yd. at	20.00	12260.00
9	Concrete, other than for Dams	25 cu. yd. at	25.00	625.00
10	Reinforcing Steel	37,300 lb. at	0.06	2238.00
11	Sheet Copper	140 lb. at	0.25	35.00
12	Asphalt Joint Filler	400 lb. at	0.10	40.00
13	No. 2 Crushed Stone, Underdrains	15 cu. yd. at	3.00	45.00
14	Stone Riprap	480 cu. yd. at	4.75	2280.00
15	4" vit. pipe - 2' lengths	14 lin.ft. at	1.00	14.00
16	Gravel Surfacing for Roads	830 cu. yd. at	1.50	1245.00
17	Gravel Surfacing for Assembly Area	85 cu. yd. at	2.00	170.00
18	Stone Masonry	64 cu. yd. at	30.00	1920.00
19	2 1/2" Galvanized Iron Pipe, Sleeves	24 lin.ft. at	1.00	24.00
20	2" Calv. Iron Pipe, Flashboard Supports	60 lin.ft. at	0.60	36.00
21	3" Oak Stop Planks	All	L.S.	15.00
22	2" Flashboards	All	L.S.	85.00
23	Water Lines	All	L.S.	640.00
24	Water Outlets	14 each at	30.00	420.00
25	Removing Pine Trees	200 trees at	1.50	300.00
26	Smoothing Assembly Area Ground	1500 sq. yd. at	0.05	75.00
27	Dowels	1050 lb. at	0.10	105.00
28	8" diam. logs for platform floor joints	120 bd. ft. at	0.30	36.00
29	14" diam. log seats	15000 bd. ft. at	0.06	900.00
30	2" Plank Floor for Speaker's Platform	580 bd. ft. at	0.10	58.00
31	Cesspools, stone-lined	3 each at	300.00	900.00
32	24" Galvanized Iron Pipe, 14-gage	64 lin.ft. at	3.00	192.00
TOTAL				\$49,820.00

Respectfully submitted

Charles H. Hurley



WHETSTONE GULF PUBLIC CAMPSITE  
ENGINEER'S ESTIMATE  
STORAGE DAM AND BATHING POOL DAM

<u>Item</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Estimated Price</u>
1WB	Applying Water	-	L.S.		
2	Unclassified Excavation		C.Y.		
2EA	Embankment in Place (Dam)		C.Y.		
2E	Embankment in Place		C.Y.		
5	Trench, Culvert and Bridge Excavation		C.Y.		
5R	Trench, Culvert and Bridge Excavation, Rock		C.Y.		
V9	Sewer Pipe (Vitrified)		L.F.		
11	Corrugated Metal Pipe		L.F.		
15-2A	Portland Cement, Type 2A		BBL.		
18	Structural Concrete		C.Y.		
24	Stone Masonry		C.Y.		
28	Bar Reinforcement for Structures		LBS.		
29	Structural Steel		LBS.		
42AB	Bottom Course-ROB Material-Loose Measure		C.Y.		
80B	Stone Rip Rap		S.Y.		
82S	Cofferdams	-	L.S.		
107A	Timber - Stop Planks		B.F.		
121	Topsoil placed from stockpiles		C.Y.		
200	No. 2 Crushed Stone Underdrain		C.Y.		
201	Furnish and Install 36" x 36" Water Control Gate	-	L.S.		
202	Bronze Grill		EA		
203	Flashboards	-	L.S.		

WHETSTONE GULF CAMPSITE  
STORAGE DAM AND BATHING POOL DAM

DETAILED SPECIFICATIONS

All contract items shall meet the requirements as set forth  
in the New York State Public Works Specifications adopted January 2,  
1957, except as may be modified under Special Specifications.

WHETSTONE GULF CAMPSITE \* STORAGE DAM AND BATHING POOL DAM

SPECIAL SPECIFICATIONS

Item 1WB - Applying Water. The specifications for Item 1WA will apply except that payment will be by lump sum.

Item 2EA - Embankment in Place - Dams.

The specifications for Item 2E will apply except as follows:

Earth embankment shall be placed in layers not more than 6" thickness and each layer thoroughly compacted as outlined in the standard specifications. There shall be no stone or rock having a maximum dimension of more than 5 inches used in embankment constructed under this item.

Item 42AB - Bottom Course-ROB Gravel-Loose Measure

The specifications for Item 42A shall apply except that the material shall be Run of Bank Gravel.

Item 80B - Dry Rip Rap

The specifications for Item 80 shall apply except as noted:

a - Materials. Dry rip rap shall consist of durable field or quarry stone each shaped as nearly as practicable in the form of a right rectangular prism. At least fifty per cent of the stones shall weigh in excess of 100 pounds each, and no stone shall weigh less than 50 pounds each. One dimension of each of the stones furnished shall be the thickness of the rip rap as shown on the plans, and the stones shall be so laid that this dimension is perpendicular to the prepared bed.

b - All dry rip rap shall be properly aligned and in close contact and shall rest on a 3 inch sand cushion. The sand cushion shall meet the requirements for cushion sand as outlined in the standard specifications Part II, "M-3 Fine Aggregates".

Item 82-S - Cofferdams

The specifications for Item 82 shall apply except that payment will be by lump sum.

Item 107-A - Timber and Lumber - Stop Planks

- a - Work. Under this item the Contractor shall furnish and place 3-inch T & G oak stop planks in the bathing pool dam as shown in the plans. The stop planks shall be made watertight by tacking sheet rubber or canvas to the upstream side of the stop planks so as to prevent water from passing under or around the ends of the stop planks, or by other approved methods.
- b - Material. Lumber furnished under this item shall be sound, square-edged, free from shakes, loose knits or decay.
- c - Measurement and Payment. The quantity to be paid for under this item shall be the number of board feet, placed in the completed work. In measuring dressed timber and lumber, the cross-section of any piece will be taken as the minimum nominal commercial size of undressed material from which the piece could have been cut. The length of any piece will be taken as the actual length in the finished work, making no deductions for bevels, notches or splices. The unit price bid will also include furnishing and installing sheet rubber, canvas or other acceptable material as outlined in paragraph "a".

Item 200 - No. 2 Crushed Stone Underdrain.

- a - Work. Under this Item the Contractor shall furnish and place No. 2 Crushed Stone Underdrains as shown on the plans. Stone shall be slightly compacted by tamping; after compaction the trenches shall be covered by one ply tar paper.

b - Material. The crushed stone shall be approved material meeting the requirements for Type A, B or C in accordance with the specifications for Crushed Stone, "M-4 Coarse Aggregates" in part II of the Standard Specifications. The stone shall be classified as No. 2 size.

c - Measurement and Payment. The quantity to be paid for under this item will be the number of cubic yards of stone measured in its final compacted position, placed as required by the plans. The cost of tar paper shall be included in the unit price bid. Excavation shall be paid for as "Trench, Culvert and Bridge Excavation, Item 5.

Item 201 - Furnish and Install 36" x 36" Water Control Gate

a - Work. Under this item the Contractor shall furnish and erect complete one 36" x 36", slide gate Armco Model 115 or equal, with 6'-0" high frame, fabricated so as not to extend above gate opening, machined cast iron slide and seat, and spigot back seat, one handwheel lift with bronze lift nut Armco HB24 or equal, one 1½" Dia. x 19" long hot rolled stem Armco or equal, 2 Armco fully adjustable stem guides or equal all necessary anchor bolts, one Locking Device Armco or equal and one Padlock Corbin Model 2863½ or equal with brass case and wrought brass shackle, lock to be supplied with two keys.

b - Payment. Payment will be made at the lump sum price bid for this item. The price bid shall include the cost of furnishing all labor, materials, and equipment necessary to complete the work to the satisfaction of the Engineer.

Item 202 - Furnish and Install Bronze Grills.

- a - Work. Under this item the Contractor shall furnish and install complete, to the satisfaction of the engineer, two approved circular cast bronze grills as indicated on the plans.
- b - Material. The grill shall have a flange and be firmly affixed to the concrete abutment. The grill shall be slotted or of other approved type, and shall have the maximum area of openings.
- c - Payment. The quantity to be paid for under this item will be the number of bronze grills furnished and installed.

Item 203 - Flashboards for Bathing Pool Dam.

- a - Work. Under this item the Contractor shall furnish and install all necessary material to construct and erect flashboards at the bathing pool dam as shown on the plans.
- b - Material. This item covers the furnishing and installing of 2" standard galvanized iron pipe sleeves, 1½" standard galvanized iron pipe flashboard supports and 2 inch T & G spruce, hemlock or yellow pine flashboards, together with all necessary hardware to affix flashboard to supports and sheet rubber or canvas to make the flashboards watertight.

The sleeves shall be accurately set as to spacing, alignment and verticality and shall be securely fastened in place so as not to be displaced while the concrete is being placed around them. The bottom of the sleeves shall be closed by caps and the tops shall be flush with the top of the concrete spillway.

Flashboards shall be made watertight by tacking sheet rubber, canvas or other approved material to the upstream side of the flashboards so as to prevent water from passing under, around the end or between the flashboards.

c - Payment. Payment for this item shall be by lump sum and shall include the complete cost of fabricating and installing the flashboard according to the plans.



DAM CONSTRUCTION PERMIT APPLICATION

STATE OF NEW YORK



DEPARTMENT OF PUBLIC WORKS

ALBANY

Received March 16, 1960 Dam No. 2862  
Disposition Approve March 30, 1960 Watershed 113-2063  
Foundation inspected \_\_\_\_\_ Black River  
Structure inspected \_\_\_\_\_

Application for the Construction or Reconstruction of a Dam

Application is hereby made to the Superintendent of Public Works, Albany, N. Y., in compliance with the provisions of Section 948 of the Conservation Law (see third page of this application) for the approval of specifications and detailed drawings, marked Whetstone Gulf Public Campsite, Storage Dam

herewith submitted for the { construction } of a dam herein described. All provisions of law will be complied with in the erection of the proposed dam. It is intended to complete the work covered by the application about October 30, 1960  
(Date)

1. The dam will be on Whetstone Creek flowing into Black River in the town of Martinsburg County of Lewis and 2-3/4 miles upstream from intersection of state hwy. 12D & Whetstone Creek.  
(Give exact distance and direction from a well-known bridge, dam, village, main cross-roads or mouth of a stream)

2. Location of dam is shown on the \_\_\_\_\_ quadrangle of the United States Geological Survey.

3. The name of the owner is NEW YORK STATE CONSERVATION DEPT.

4. The address of the owner is Albany, N. Y.

5. The dam will be used for Stream Regulation & Flood Control

6. Will any part of the dam be built upon or its pond flood any State lands? Yes

7. The watershed above the proposed dam is 8.1 square miles.

8. The proposed dam will create a pond area at the spillcrest elevation of 380 acres and will impound 60 million cubic feet of water.

9. The maximum height of the proposed dam above the bed of the stream is.....17.....feet.....--.....inches.
10. The lowest part of the natural shore of the pond is.....0.....feet vertically above the spillcrest, and everywhere else the shore will be at least.....0.....feet above the spillcrest.
11. State if any damage to life or to any buildings, roads or other property could be caused by any possible failure of the proposed dam. No damage other than flooding of state-owned land is contemplated
12. The natural material of the bed on which the proposed dam will rest is (clay, sand, gravel, boulders, granite, shale, slate, limestone, etc.)...../ Clay & gravel
13. Facing downstream, what is the nature of material composing the right bank?.....Clay & gravel
14. Facing downstream, what is the nature of the material composing the left bank?.....Clay & gravel
15. State the character of the bed and the banks in respect to the hardness, perviousness, water bearing, effect of exposure to air and to water, uniformity, etc. There is no evidence of bedrock at the dam site. Under 9 to 12 inches of topsoil the soil is fairly impervious mixture of clay and gravel
16. Are there any porous seams or fissures beneath the foundation of the proposed dam?.....No
17. WASTES. The spillway of the above proposed dam will be.....60.....feet long in the clear; the waters will be held at the right end by an earth embankment.....the top of which will be.....5.....feet above the spillcrest, and have a top width of.....8.....feet; and at the left end by an earth embankment.....the top of which will be.....5.....feet above the spillcrest, and have a top width of.....feet.
18. The spillway is designed to safely discharge.....334.....cubic feet per second.
19. Pipes, sluice gates, etc., for flood discharge will be provided through the dam as follows:  
One 3' x 3' oriface with 36" x 36" slide gate. Oriface is to be located  
2'-0 off right end
20. What is the maximum height of flash boards which will be used on this dam? NONE
21. APRON. Below the proposed dam there will be an apron built of Reinforced concrete 35'6" feet long across the stream,.....60.....feet wide and 1'0" & 1'6" feet thick.
22. Does this dam constitute any part of a public water supply?.....No

PREVIOUS REPORTS



## New York State Department of Environmental Conservation

## M E M O R A N D U M

TO: THE FILES  
FROM: G. Koch  
SUBJECT: Dam at Whetstone Gulf State Park - #101-2862 Black River  
DATE: June 11, 1976

The present operating procedure on the dam involves draining the lake in the Fall to provide storage for Spring run-off. Burrell Puffington, biologist from Watertown requested that minimum water surface be kept at about 4 feet below spillway crest in order to provide a lake for fish.

My hydrologic investigation indicates that when water surface is at spillway crest the reservoir provides a large amount of flood storage and I, therefore, recommended that the water surface be raised to the level requested by Mr. Puffington. This information was conveyed to the three members of the Thousand Island State Park Commission and they agreed to comply with the higher water surface to provide for fishing in the reservoir. The water surface has to be kept below the spillway crest because at this level, an upstream dike will be overtopped.

The concrete spillway was in good condition. During the Fall of 1975 it was grouted with epoxy cement. I informed the Park Commission that maintenance should be performed on the earth embankment so that the top of the dam is level with the top of wall on the spillway. The earth presently drops down 2 feet at the intersection of the wall and top of dam.

WHAISTONE GULF DAM


#113-2863

D.A. = 8.1 Sq Mi

Surface Area = 380 Acres

Reservoir = 60 Million C.F.

$$Vol = \frac{60,000,000}{43,560} = 1500 \text{ A.F.}$$

SPILLWAY

$$Q = CLH^{3/2}$$

$$Q = 3.1 (60) (3)^{3/2}$$

$$Q = 960 \text{ cfs}$$

$$\text{Peak Inflow} = 35 \times 8.1 = 285 \text{ cfs}$$

DESIGN FLOOD

$$100 \text{ Yr} - 6 \text{ Hr} \quad P = 3.7$$

RUNOFF

$$\left. \begin{array}{l} P = 3.7 \\ W = 70 \end{array} \right\} R = 1.1$$

$$Vol \text{ Runoff} = \frac{1.1}{12} \times 8.1 \times 640 = 480 \text{ A.F.}$$

SUMMARY: O.K. TO RAISE W.S. TO SPILLWAY CREST (1898.0)

$$\text{Storage} = 1140 \text{ A.F.} \quad \text{Runoff } 100 \text{ Yr} = 480 \text{ A.F.}$$

PREVIOUS INSPECTION REPORTS

# STATE OF PARKS AND RECREATION STRUCTURE INVENTORY

1970

1. Name of Structure

Location of Park County Area	Name of Lake or River	Type of Dam			Dimensions		Capacity Acres Ft.	Water Retained Sq. Miles	Purpose or Use	Year Built	Condition			When was last inspected
		Concrete	Other	Other	L	H					1	2	3	
St. Lawrence State Park	Sprinkled Creek				20'	7'	35+		Fish & Wild- life Refuge Trail	1970	X			1/10/70 R.D. Healy
Postville Golf Course - Postville	Black River Basin, What- stone Creek				40'	20'	10,000+		Water Supply Recreational Fish & Wild- life Flood Control	1960	X			1/6/70 R. Gerry
Postville Golf Course - Postville	Black River Basin, What- stone Creek	X			30'	10'	5+		Swimming	1960	X			1/5/70 R. Gerry
Postville Island State Park - Postville Center	St. Lawrence River Basin Stream				700'	14'	63+		Fish & Wild- life Refuge Trail	1971	X			1/1/70 R. W. Kelley
Postville Carver State Park	St. Lawrence River Basin			X (Fence stone filled in on both sides with concrete overflow)	15'	15'	5+		Fish & Wild- life					(See Remarks)

Comments: Several dams are actually no longer there. Timber cribbing, etc., very poor and in all visible areas.



OFFICE OF PARKS AND RECREATION  
DAM STRUCTURE INVENTORY

Region: Thousand Islands

Page: 1 OF 4

Location of Park or Other Area	Name of Lake	Type of Dam			Dimensions		Capacity Acre Fr.	Water Shed Sq. Feet	Purpose or Use	Year Built	Condition			When and by whom was dam last inspected?
		Mass	Earth	Other	L	W					G	F	P	
Killesley Island Nature Center	St. Lawrence River Basin Stream		X		310'+ 535'+	3'+ 145'+	63+		Fish & Wildlife Nature Trail	1971	X			7/79 L. Geoghegan (see attached)
Jacques Cartier State Park	St. Lawrence River Basin Stream			X Stone filled timber crib abutments wooden dam	15'+	15'+	5+		Fish & Wildlife	Circa 1963			X	7/79 L. Geoghegan (see attached)
St. Lawrence State Park Golf Course	Pond		X		25'+	15'+	1 1/2+		Wildlife & Golf Course	1969		X		7/79 L. Geoghegan (see attached)
Hipley Flow State Park	Spring Fed Creek		X		20'+	7'+	35+		Fish & Wildlife Nature Trail	1970		X		7/79 L. Geoghegan (see attached)
Whetstone Gulf State Park - Upper	Black River Basin Whetstone Creek	X			40'+	20'+	10,000+		Water Supply Recreational Fish & Wildlife Flood Control	1959		X		7/79 L. Geoghegan (see attached)

OFFICE OF PARKS AND RECREATION  
DAM STRUCTURE INVENTORY

REGION: Thousand Islands

PAGE: 4 OF 4

5) Whetstone Gulf State Park Dam - Upper

This is a concrete dam with concrete abutments, spillways, etc.

- a) The lower portion of the concrete abutment wall, adjacent to the spillway shows erosive wear and spalling. This should be corrected at this time.

6) Macomb Reservation State Park Dam

This is a concrete dam with concrete abutments, spillways, etc.

- a) Trees existing on adjacent earthen embankments.
- b) Scaling and spalling of concrete increasing on lower spillway vertical walls.
- c) Control gate hand wheel still missing.

These are the exact same problems revealed by last year's inspection. To date nothing has been done.

Again we also request one of the dam experts from D.E.C. inspect this structure.

1981

OFFICE OF PARKS AND RECREATION  
DAM STRUCTURE INVENTORY

Region 1000 ISLANDS

Location (Park or Area)	Name of Lake	Type of Dam			Dimensions		Capacity Acre Ft.	Water Shed Sq. Miles	Purpose or use	Year Built	Condition			When and by whom was dam last inspected?
		Mas.	Earth	Other	L	H					G	F	P	
St. Lawrence State Park Golf Course	NO NAME		X		25'±	15'±	1/2±		Wildlife & Golf Course Hazard-fire Protection	1969 rebuilt 1981			X	7/80 L. Seoghegan (See Attached)
Jacques Cartier State Park	St. Lawrence River Basin Stream				ABANDONED - DEMOLISHED		REMOVED FROM		INVENTORY					SEE ATTACHED
Whetstone Golf State Park Lower	Black River Basin - Whet- stone Creek				40'±	20'±	10,000+		Water supply Recreational Fish & Wildlife Control	1951		X		7/80 L. Seoghegan (See Attached)
Whetstone Golf State Park Lower	Black River Basin - Whet- stone Creek				30'±	10'±	5+		Swimming	1951				7/80 L. Seoghegan
Macomb Reser- vation State Park	Salmon River Basin Stream				20'±	15'±	120+		Recreation Fish & Wildlife	1950				7/80 L. Seoghegan (See Attached)

OFFICE OF PARKS & RECREATION  
DAM STRUCTURE INVENTORY

REGION: THOUSAND ISLANDS

1) St. Lawrence State Park Golf Course

This dam was rebuilt in the spring of 1981. The overflow/intake structure consists of 4' - 0" diameter RCCP manhole riser sections, covered by a steel-grid trash rack. Connected to the bottom MH section is 30" diameter RCCP which carries through the earthen dam to an end section and is spilled over large stones. Approximately 20' from the manhole riser along the 30" RCCP, a concrete anti-seep collar was constructed.

2) Jacques Cartier State Park

This dam was demolished and removed from our inventory.

3) Whetstone Gulf State Park (Upper)

The lower portion of the concrete abutment wall, adjacent to the spillway is scheduled for repair after Labor Day.

4) Macomb Reservation State Park

At the time of inspection, heavy rain precluded taking photos. These will be forwarded at a later date.

The deficiencies and corrections since last years report:

- a) Trees on earthen embankment have been removed.
- b) Scaling & spalling on lower spillway vertical walls has not increased. Cracks identified for observation and possible treatment in DEC Inspection Report were monitored over last fall and winter. Observations indicate no further movement is occurring. Cracks to be repaired 9/81.
- c) Control gate hand wheel and flanged gate adapter restored 6/81. Control gate is functional.
- d) No further problems observed.

5) Wellesley Island State Park Nature Center

Last year's deficiencies were corrected. Mowing and general maintenance takes place annually after July 1. This enables all nesting birds and animals to be clear of the areas to be maintained.

APPENDIX F


REFERENCES

## REFERENCES



1. Chow, Ven Te, Editor - Handbook of Applied Hydrology. McGraw-Hill Book Company, New York, New York, 1964.
2. Hydrologic Engineering Center, U.S. Army Corps of Engineers, HEC-1 Flood Hydrograph Package, Users Manual. Davis, California, January 1973.
3. Hydrologic Engineering Center, U.S. Army Corps of Engineers, Flood Hydrograph Package (HEC-1), Users Manual for Dam Safety Investigations, Davis, California, September 1978.
4. King, Horace and Brater, Ernest. Handbook of Hydraulics, 5th Edition. McGraw-Hill Book Company, New York, New York, 1963.
5. Riedel, J.T., Appleby, J.F. and Schloemer, R.W. Seasonal Variation of the Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1000 Square Miles and Durations of 6, 12, 24, and 48 Hours (Hydrometeorological Report No. 33) U.S. Department of Commerce - Weather Bureau and U.S. Department of the Army - Corps of Engineers, Washington, D.C., April 1956
6. U.S. Department of the Interior, Bureau of Reclamation, Design of Small Dams, Second Edition, Washington, D.C., 1973.

APPENDIX G

DRAWINGS







STATE OF NEW YORK  
DEPARTMENT OF PUBLIC WORKS  
DIVISION OF CONSTRUCTION  
ALBANY, N. Y.





This plan for WHETSTONE GULF PUBLIC CAMPSITE  
is submitted to the Board of Supervisors of Lewis County, New York, for their consideration and approval.

APPROVED: Charles H. Hurley  
CHIEF ENGINEER  
DIVISION OF PUBLIC WORKS




DATE: 10/1/58

101-2842- BLACK


WHETSTONE GULF PUBLIC CAMPSITE NEAR LOWVILLE LEWIS COUNTY - NEW YORK		
Drawn by C. H. H.	CONSTRUCTION	Scale: AS SHOWN
Checked by E. A. H.	PUBLIC CAMPSITE DEVELOPMENT	Scale: AS SHOWN
Reviewed by C. H. H.	TOPOGRAPHY OF STONE BASIN AND DAM SITE AND ROAD IMPROVEMENT DESIGN	Scale: AS SHOWN
Checked by C. H. H.	CHARLES H. HURLEY CONSTRUCTION DEPT. DIVISION OF LAND & FORESTS	Scale: AS SHOWN




TYPICAL CROSS SECTION OF




WATER GATE CAMP SITE	
YEAR 1943	
Drawn by R.D.S.	CONSTRUCTION
Traced by R.D.S.	PL. AND SITE DESIGN
	TOTAL CURVES
BUREAU OF CAMPS & TRAILS	
CONSTRUCTION DEPARTMENT	
DIVISION OF LANDS & FORESTS	
2 of 5	



PLAN OF STORAGE DAM  
SCALE 1"=20'




SECTION B-B  
UPSTREAM ELEVATION OF DAM  
SCALE 1"=40'



SECTION A-A  
SCALE 1"=40'

SCALE 1"=4'-0"  
TYPICAL FOR ALL EXPANSION




SECTION C-C & D-D

SCALE 1" = 4'-0"


**EAST ABUTMENT-SECTION C-C**

EAST WINGWALL - SECTION D-D

மேலும், கீழ்க்கண்டவற்றைப் பற்றித் தகவல் அளிப்பதற்காகக் கேள்வி எழுப்பப்படுகிறது.



SECTION E-E



SECTION OF  
SPILLWAY  
5648/1047

**No 725**

Case no. 22 Antonio Garza, Mex. 113 on Exam. 31 Oct 57 (1957)

From the 1st of 6th Floor, the view of the river and the city was very good.

GATE NO. 3 IN POSITION BEHIND PERMANENT JAILWAY

DATE SUBMITTED FOR THE YEAR 2000 IN THE STATE OF TEXAS

ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED


4. Examine the following statements and give reasons for your answer.

A. Remondino was "very, friendly" today

Continued to read 3 1/2" story to bottom edge to completion of 2nd story  
down to 1st floor.


See page 4 for more information on this report.

1998, 1999, 2000, 2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010, 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018, 2019, 2020, 2021, 2022, 2023, 2024, 2025, 2026, 2027, 2028, 2029, 2030, 2031, 2032, 2033, 2034, 2035, 2036, 2037, 2038, 2039, 2040, 2041, 2042, 2043, 2044, 2045, 2046, 2047, 2048, 2049, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2059, 2060, 2061, 2062, 2063, 2064, 2065, 2066, 2067, 2068, 2069, 2070, 2071, 2072, 2073, 2074, 2075, 2076, 2077, 2078, 2079, 2080, 2081, 2082, 2083, 2084, 2085, 2086, 2087, 2088, 2089, 2090, 2091, 2092, 2093, 2094, 2095, 2096, 2097, 2098, 2099, 2100, 2101, 2102, 2103, 2104, 2105, 2106, 2107, 2108, 2109, 2110, 2111, 2112, 2113, 2114, 2115, 2116, 2117, 2118, 2119, 2120, 2121, 2122, 2123, 2124, 2125, 2126, 2127, 2128, 2129, 2130, 2131, 2132, 2133, 2134, 2135, 2136, 2137, 2138, 2139, 2140, 2141, 2142, 2143, 2144, 2145, 2146, 2147, 2148, 2149, 2150, 2151, 2152, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2160, 2161, 2162, 2163, 2164, 2165, 2166, 2167, 2168, 2169, 2170, 2171, 2172, 2173, 2174, 2175, 2176, 2177, 2178, 2179, 2180, 2181, 2182, 2183, 2184, 2185, 2186, 2187, 2188, 2189, 2190, 2191, 2192, 2193, 2194, 2195, 2196, 2197, 2198, 2199, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209, 2210, 2211, 2212, 2213, 2214, 2215, 2216, 2217, 2218, 2219, 2220, 2221, 2222, 2223, 2224, 2225, 2226, 2227, 2228, 2229, 2230, 2231, 2232, 2233, 2234, 2235, 2236, 2237, 2238, 2239, 2240, 2241, 2242, 2243, 2244, 2245, 2246, 2247, 2248, 2249, 2250, 2251, 2252, 2253, 2254, 2255, 2256, 2257, 2258, 2259, 2260, 2261, 2262, 2263, 2264, 2265, 2266, 2267, 2268, 2269, 2270, 2271, 2272, 2273, 2274, 2275, 2276, 2277, 2278, 2279, 2280, 2281, 2282, 2283, 2284, 2285, 2286, 2287, 2288, 2289, 2290, 2291, 2292, 2293, 2294, 2295, 2296, 2297, 2298, 2299, 2300, 2301, 2302, 2303, 2304, 2305, 2306, 2307, 2308, 2309, 2310, 2311, 2312, 2313, 2314, 2315, 2316, 2317, 2318, 2319, 2320, 2321, 2322, 2323, 2324, 2325, 2326, 2327, 2328, 2329, 2330, 2331, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340, 2341, 2342, 2343, 2344, 2345, 2346, 2347, 2348, 2349, 2350, 2351, 2352, 2353, 2354, 2355, 2356, 2357, 2358, 2359, 2360, 2361, 2362, 2363, 2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371, 2372, 2373, 2374, 2375, 2376, 2377, 2378, 2379, 2380, 2381, 2382, 2383, 2384, 2385, 2386, 2387, 2388, 2389, 2390, 2391, 2392, 2393, 2394, 2395, 2396, 2397, 2398, 2399, 2400, 2401, 2402, 2403, 2404, 2405, 2406, 2407, 2408, 2409, 2410, 2411, 2412, 2413, 2414, 2415, 2416, 2417, 2418, 2419, 2420, 2421, 2422, 2423, 2424, 2425, 2426, 2427, 2428, 2429, 2430, 2431, 2432, 2433, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2441, 2442, 2443, 2444, 2445, 2446, 2447, 2448, 2449, 2450, 2451, 2452, 2453, 2454, 2455, 2456, 2457, 2458, 2459, 2460, 2461, 2462, 2463, 2464, 2465, 2466, 2467, 2468, 2469, 2470, 2471, 2472, 2473, 2474, 2475, 2476, 2477, 2478, 2479, 2480, 2481, 2482, 2483, 2484, 2485, 2486, 2487, 2488, 2489, 2490, 2491, 2492, 2493, 2494, 2495, 2496, 2497, 2498, 2499, 2500, 2501, 2502, 2503, 2504, 2505, 2506, 2507, 2508, 2509, 2510, 2511, 2512, 2513, 2514, 2515, 2516, 2517, 2518, 2519, 2520, 2521, 2522, 2523, 2524, 2525, 2526, 2527, 2528, 2529, 2530, 2531, 2532, 2533, 2534, 2535, 2536, 2537, 2538, 2539, 2540, 2541, 2542, 2543, 2544, 2545, 2546, 2547, 2548, 2549, 2550, 2551, 2552, 2553, 2554, 2555, 2556, 2557, 2558, 2559, 2560, 2561, 2562, 2563, 2564, 2565, 2566, 2567, 2568, 2569, 2570, 2571, 2572, 2573, 2574, 2575, 2576, 2577, 2578, 2579, 2580, 2581, 2582, 2583, 2584, 2585, 2586, 2587, 2588, 2589, 2590, 2591, 2592, 2593, 2594, 2595, 2596, 2597, 2598, 2599, 2600, 2601, 2602, 2603, 2604, 2605, 2606, 2607, 2608, 2609, 2610, 2611, 2612, 2613, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2630, 2631, 2632, 2633, 2634, 2635, 2636, 2637, 2638, 2639, 2640, 2641, 2642, 2643, 2644, 2645, 2646, 2647, 2648, 2649, 2650, 2651, 2652, 2653, 2654, 2655, 2656, 2657, 2658, 2659, 2660, 2661, 2662, 2663, 2664, 2665, 2666, 2667, 2668, 2669, 2670, 2671, 2672, 2673, 2674, 2675, 2676, 2677, 2678, 2679, 26




DETAILS OF LONGITUDINAL SILL  
SCALE 1/4" = 1'-0"


WHEATSTONE GULF DUAL CAMPSITE	
STARLOWREE LEWIS COUNTY, NEW YORK	
Collected By R.A.N. T. J. J. R.A.N.	COUNTY PUB. LANDS DEVELOPMENT ELEVATION DETAILS OF TERRAIN BUREAU OF CAMPS & TRAILS CONSERVATION DEPT DIVISION OF LAND & FORESTS
Date Jan. 1916 5-1/2 48 ft 10 ft	3-1/2




SECTION F-F  
ELEVATION OF CANTILEVERED BEAM  
SCALE 1/2" = 1'-0"



SECTION A-A  
DETAILS OF RAILING  
SCALE 1/2" = 1'-0"




SECTION B-B  
SCALE 1/2" = 1'-0"





LOCATION OF CANTILEVER SLAB  
SCALE 1"=10'-0"


WHETSTONE GOLF PUBLIC CAMPSITE NEAR LOWVILLE LEWIS COUNTY - NEW YORK		
DRAWN BY R.B.N. TRACED BY E.R.C.	CONSTRUCTION	
	PUBLIC CAMPSITE DEVELOPMENT	DATE JUN 1961
	DETAILS OF CANTILEVER SLAB	SCALE AS SHOWN Drawing No.
	BUREAU OF CAMPS&TRAILS CONSERVATION DEPARTMENT DIVISION OF LANDS & FORESTS	4 of 5
REVISIONS:		
Approved by <u>Engineering Consultant</u> Date <u>        </u>		



TYPICAL CROSS SECTION OF BATHING POOL DAM  
Scale 1/4" = 1'-0"







R34